

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:	Repair and maintenance of 11kV OH Line from KDH Old Substation to Rohini main Substation under Rohini Project, NK Area	NIT No. GM (NK)/EnM/eNIT/2024-25/112; dated 14.11.2025.			
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of steel tubular or rail pole struct in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required. Above 10.00 meters and up to 11.00 meter.	5.00	Nos		0.00	INR Zero Only
2	Erection of all aluminium conductor of 7/3.40 mm to 7/4.00 mm diameter and above including binding etc as required.	409.29	kg		0.00	INR Zero Only
3	Supplying and erection of stay set complete (galvanized) with 19/ 20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, bow tightener, 7/ 4.00 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	7.00	Set		0.00	INR Zero Only
4	Supply of clamps, bolts, nuts etc.	20.00	Set		0.00	INR Zero Only

5	Erection of disc / pin insulator for 11 KV over head lines as required.	30.00	Set		0.00	INR Zero Only
6	Erection of pole top / straight two wire/ V shape two wire, angle iron / channel iron, cross arm on steel tubular/ rail/ PCC pole for 11/22/33 KV as required.	10.00	Set		0.00	INR Zero Only
7	Supply of 6 SWG G.I. wire	400.00	kg		0.00	INR Zero Only
8	Erection of 8/6 SWG GI wire including binding etc. as required.	215.00	kg		0.00	INR Zero Only
9	Dismantling of pole / street light standard /strut embedded in cement concrete foundation etc. as required.	5.00	Nos		0.00	INR Zero Only
10	Supply and erection of 11 kV pin insulator complete with large steel headlines as required.	18.00	Set		0.00	INR Zero Only
11	Erection of cradle Guard as required.	240.00	Nos		0.00	INR Zero Only
12	Earthing with G.I. earth plate 600 mm x 600 mm x 6 mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 mtrs long etc etc. with charcoal and salt as required.	5.00	Set		0.00	INR Zero Only
13	Dismantling of over head lines comprising of copper / aluminium over head conductor, G.I. wire, cross arms, insulators etc as required	322.00	kg		0.00	INR Zero Only
14	Tree treeming/ branch cutting under overhead lines.	7200.00	sqmtr		0.00	INR Zero Only
15	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				