

Tender Inviting Authority: Safety Officer,Birsa Project , Barka-Sayal Area, CCL.

Name of the Work	Providing and installing of 80 nos. of iron/retro reflective safety board for safety related slogans as desired during safety week and DGMS inspection in Birsa Project / North Urimari OCP.					
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By Cl./Subsidiary (in Rs.)
Name of the Bidder/ Bidding		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	9.72	cum			0.00	INR Zero Only
2	1:3:6 (1 cement : 3 manufactured sand derived from Recycled concrete Aggregate (RCA) : 6 graded stone aggregate 20 mm nominal size Recycled Aggregate (RA))	9.72	cum			0.00	INR Zero Only
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	2069.68	kg			0.00	INR Zero Only
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	255.42	sqm			0.00	INR Zero Only
5	Lettering with black Japan paint of approved brand and manufacture	20000.00	per letter per cm height			0.00	INR Zero Only
6	Retro-reflectorised Traffic signs (Providing and fixing of retr - reflectorised cautionary, mandatory and informatory sign as per IRC :67 made of encapsulated lens type reflective sheeting vide clause 801.3, fixed over aluminium sheeing, 1.5 mm thicj supported on a mild steel angle iron post 75mm x 45mm x 6mm, firmly fixed to the ground by means of properly disgned foundation with M15 grade cement concrete 45cm x 45cm x 60cm, 60cm, below ground level as per approved drawing) 80cm x 60cm x 2.4 m rectangular.	30.00	each			0.00	INR Zero Only
7	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work 65 mm dia nominal bore	219.00	meter			0.00	INR Zero Only
8	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 50 to 80 mm nominal bore	350.00	each			0.00	INR Zero Only
9	Total Impact of GST for the purpose of CTC	1.000	No.		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					