

Tender Inviting Authority: Project Engineer(EnM),Urimari OCP, Barka-Sayal Area, CCL.						
Name of the Work / Contract No:	Day to Day maintenance of LT and HT overhead transmission and distribution line on as and when required basis for a period of one year(365) days under Urimari OCP.			NIT No. : PE(EnM)/Urimari/e Tender/25-26/34		Dated: 17/11/2025
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of metallic pole of above 08 Mtr and upto 10.00 Mtr length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	70.00	No.		0.00	INR Zero Only
2	Supplying and erection of stay set complete (galvanised) for 11KV overhead lines with 19/ 20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle (20 mm X 60 cm), 7/ 4.00 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	25.00	Set.		0.00	INR Zero Only
3	Supplying of two lengths channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre)cross arm for two 11KV over head line conductors with 50mm x 50mm x 6mm(Angle iron bracket welded to the channel iron) and complete with 50mm x 6mm MS flat iron clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	30.00	Set.		0.00	INR Zero Only
4	Erectionof Angle iron/channel iron cross arm on wood/RCC/PCC/steel tubular/rail pole etc. as required.	55.00	No.		0.00	INR Zero Only
5	Supply and Erection of 75 mm x 90mm Shackle Insulator Complete with G.I. Spindle, bolts,nuts and straps etc. as required.	60.00	No.		0.00	INR Zero Only
6	Supply and Erection of 100 mm x 65mm Pin Insulator Complete with G.I. Spindle and nuts as required.	60.00	No.		0.00	INR Zero Only
7	Erection of LV/MV shackle/pin insulator etc. as required	110.00	No.		0.00	INR Zero Only
8	Erection of ACSR conductor of 7/2.11 mm to 7/3.00 mm diameter and above including binding etc. as required	2,568.00	Kg.		0.00	INR Zero Only
9	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 mm diameter and above including binding etc. as required	3,546.00	Kg.		0.00	INR Zero Only
10	Erection of GI wire no 8 SWG including binding etc as required.	363.00	Kg.		0.00	INR Zero Only
11	Erection of Cradle Guard as required	480.00	No.		0.00	INR Zero Only
12	Erection of pole top/straight two wire/v shape two wire, angle iron/ channel iron, cross arm on steel tubular/ rail/PCC pole for 11/22/33KV as required.	30.00	No.		0.00	INR Zero Only
13	Supplying and erection of 33KV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required	30.00	Set.		0.00	INR Zero Only
14	Supplying and erection of 11KV disc insulator for 11KV overhead lines with galvanised insulator fittings, ball and socket type complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	30.00	Set.		0.00	INR Zero Only
15	Erection of Disc/pin insulator for 11KV overhead lines as required.	30.00	Set.		0.00	INR Zero Only
16	Dismantling of over head lines comprising of copper/ aluminium overhead conductor, G.I. wire, cross arms, insulators etc. as required.	3,139.00	Kg.		0.00	INR Zero Only
17	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required.	60.00	No.		0.00	INR Zero Only
18	Supply of 08 SWG GI wire	584.00	Kg.		0.00	INR Zero Only

19	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre)cross arm for two 33KV overhead line conductors complete with 50mm x 50mm x 6mm(Angle iron bracket welded to the channel iron) and complete with 50mm x 6mm MS flat iron clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	20.00	No.		0.00	INR Zero Only
20	Loading,Transporting and unloading of dismantled material from site to store.	1.00	Lot.		0.00	INR Zero Only
21	Total impact of GST for the purpose of CTC	1.000	Nos.	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

