

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:	Dismantling and erection, transporting, repairing, strengthening and fabrication of the weighment platform structure of KDH Road weighbridge No.- 01/Purnadih WB No. 03, Make – ORION, Sl. No.- 13P-1302 along with installation of Lightning arrestor and making platform structure for load cell only at new location under Purnadih OCP, NK Area		NIT No. GM (NK)/EnM/eNIT/2025-26/117; dated 18.11.2025.		
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Part – A (INSTALLATION OF LIGHTNING ARRESTOR WORK)					
2	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. Above 11 meter and upto 13 meter	4.00	Nos		0.00	INR Zero Only
3	Providing and fixing 25 mm X 5 mm GI. Strip on surface or in recess for connection etc. as required	60.00	Mtr		0.00	INR Zero Only
4	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required.	145.00	Mtr		0.00	INR Zero Only
5	Providing and fixing 25 mm X 5 mm copper Strip on surface or in recess for connection etc. as required	30.00	Mtr		0.00	INR Zero Only

6	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	7.00	Nos		0.00	INR Zero Only
7	Providing of lightning arrestor.	4.00	Set		0.00	INR Zero Only
8	Providing of DMC/Epoxy electrical insulator with nut bolt and washers.	32.00	Nos		0.00	INR Zero Only
9	Labour cost on item no. 7 & 8	1.00	job		0.00	INR Zero Only
10	Pole painting two coats. (Aluminum Paint)	4.00	Nos		0.00	INR Zero Only
11	Part – B (CIVIL WORK FOR FOUNDATION OF WEIGHMENT STRUCTURE)					
12	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5m in width or 10sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	32.45	Cum		0.00	INR Zero Only
13	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	25.50	Cum		0.00	INR Zero Only
14	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement :4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	43.52	Cum		0.00	INR Zero Only
15	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 Cement :2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	16.81	Cum		0.00	INR Zero Only
16	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1726.90	kg		0.00	INR Zero Only
17	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	506.65	kg		0.00	INR Zero Only
18	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 cement: 4 fine sand)	50.00	Sqm		0.00	INR Zero Only
19	Steel S5310 dia. M24 1000mm foundation bolts.	16.00	Nos		0.00	INR Zero Only

20	Assorted cutting & welding of R.S. Joist and M.S. Plates & Strips.	789.40	Mtr		0.00	INR Zero Only
21	Scrubbing, cleaning and painting of weighing platform structure.	185.00	Sqm		0.00	INR Zero Only
22	Drilling of attached M.S plate and Joist.	96.00	Nos		0.00	INR Zero Only
23	Providing of nut, bolt 5/8 x 3"	35.17	kg		0.00	INR Zero Only
24	Providing of washers 5/8	7.50	kg		0.00	INR Zero Only
25	Providing of nut, bolt & washers 30/32 x 6"	60.00	Nos		0.00	INR Zero Only
26	Providing of G.I pipe 2".	115.00	ft		0.00	INR Zero Only
27	Providing of G.I bend 2".	6.00	Nos		0.00	INR Zero Only
28	Providing of G.I L bend 2".	4.00	Nos		0.00	INR Zero Only
29	CPOH on item no. 22 to 28.	1.00	job		0.00	INR Zero Only
30	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				