Validate	Print Help Item	Rate BoQ					
Tender Inviting Authority:	P.E (E&M)/Kedla Washery.						
Name of the Work / Contract No:	Electrical wiring of security of security barrack and partial rewiring of administrative building, battery room, executive rest house of Kedla Washery.  NIT No-PO/KWIE-Tender/25-26/57 date:- 18.11.2025						
	Category of Services (To Be Selected by Department)		Category of Bidder ( To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.00
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER#	TEXT #	NUMBER#	TEXT#	NUMBER	NUMBER#	NUMBER #	TEXT#
SI. No.		Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P		TOTAL AMOUNT In Words
1	2	3	4	5	6	7	0
1	Wiring for light point/fan point/exhaust fan point/call ball point with 1.5 sq. mm RRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit, with plano type switch phenolic laminated sheet, sultable size M. S. box and earthing the point with 1.5sq. mm PRLS PVC insulated copper conductor single core cable etc as required.	190.00		5	6		iNR Zero Only
2	Supplying and fixing metal box of 150mmX 75mmX60mm deep (nominal size) opn surface or iun recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 A socket outlet and 5/6 A plano type switch, connections, painting etc. as required.	60.000					INR Zero Only
3	Supplying and fixing metal box of 150mmX 75mmX60mm deep (nominal size) opn surface or iun recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 A socket outlet and 5/6 A plano type switch, connections, painting et as required.	45.000	Nos.			0.00	INR Zero Only
4	Supplying and fixing two module stepped type electronic fan requlator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	36.000				0.00	INR Zero Only
	Supplying and fixing 5A to 32A rating 240/415 V, 10KA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MOB DB complete with connections, testing and commissioning etc. as required double.	28.000				0.00	INR Zero Only
6	Supplying and fixing following rating, double pole, 240V, isolator in the existing MOB DB complete with connection testing and commissioning etc. as required.	10.000				0.00	INR Zero Only
7	Wiring for light circuit/submain alongwith earth wire with the following sizes of FRIS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2X4sq.mm + 1X4sqmm.	370.000				0.00	INR Zero Only
8	Supplying and fixing call bell/ buzzer suttable for single phase,					0.00	INR Zero Only
9	230V, complete as required.  Supplying and fixing following rating four pole, 415V, Isolator in the existing MOB DB complete with connections, testing	10.000				0.00	INR Zero Only
10	and commisioning et as required. 63A Supplying, Installing, testing and commissioning of following capacity TPN tap off box made of 1.6mm thick sheet steel enclosure dulypainted with power coating on existing rising mains complate with TPN disconnector FSU and HRC fuses, connections, earthings et as requied 100A TPN.	3.000 1.000				0.00	INR Zero Only
11	Total impact of GST for the purpose of CTC	1.00			0.00	0.00	INR Zero Only
Total in Figures			<u>I</u>	<u>I</u>		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					