

Tender Inviting Authority: Project Engineer(E&M), Bhurkunda Colliery, Barka-Sayal Area, CCL.							
Name of the Work / Contract No:		Electrical re-wiring of residential quarter no. 2A/02, 2CR/07 and CCL K S union office BMS under Bhurkunda Project.			NIT No. : PE(EnM)/BHK/e Tender/25-26/36 Dated: 26.11.2025		
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected)					
Works Contract		Bidder's Status (Mandatory)		Total GST(in Rs.)		GST to be Paid By Bidder (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select		0.00		0.00	
						0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	12	6	7	8
1	Wiring for light point Fan Point/Exhaust fan point/Call bell point with 1.5 sq.mm FR PVC insulated copper conductor single core cable in surface/recessed PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S box and earthing the point with 1.5sq.mm FR PVC insulated copper conductor single core cable etc as required	184	Nos.	INR		0.00	INR Zero Only
2	Wiring Circuit/sub-main wiring in PVC conduit : wiring for circuit/sub-main wiring along with earth wire with following size of PVC insulated copper conductor, single core cable in surface/recessed PVC conduit as required (2x2.5sq.mm + 1x2.5sq.mm earth wire)	280	Mtrs.	INR		0.00	INR Zero Only
3	Wiring Circuit/Sub-main wiring in PVC conduit; wiring for circuit / sub-main wiring along with earth wire with following size of PVC insulated copper conductor, single core cable in surface/recessed PVC conduit as required(2x4sq.mm+1x4sq.mm earth wire)	250	Mtrs.	INR		0.00	INR Zero Only
4	S/F Piano type switch/Socket: Supply & fixing following piano type switch/Socket on the existing switch box/cover including connection as required (3Pin5/6 Amp. Socket) outlet.	51	Nos.	INR		0.00	INR Zero Only
5	200mm X 250mm X 75mm deep PVC box etc. as required	6	Nos.	INR		0.00	INR Zero Only
6	200mm X 150mm X 75mm deep PVC box etc. as required	35	Nos.	INR		0.00	INR Zero Only
7	S/F power plug point piano type accessories supply & fixing metal box of 180mm x100 x60mm deep (Nominal Size) on surface or recess or in recies with suitable size of phenolic laminated sheet cover in front including providing & fixing in 5/6 & 15/16 Amp Socket outlet and	35	Nos.	INR		0.00	INR Zero Only
8	S/F ceiling rose: Supply & Fixing 3 Pin, 5 Amp Rose on the existing junction Box/ wooden box including connection etc as required.	64	Nos.	INR		0.00	INR Zero Only
9	S/F brass holder: Supply & Fixing brass batten / angle bolder including connection etc. as required	69	Nos.	INR		0.00	INR Zero Only
10	Supplying and fixing Samps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.(Double Pole)	9	Nos.	INR		0.00	INR Zero Only
11	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 2 + 4way / 6way, Double door.	9	Nos.	INR		0.00	INR Zero Only
12	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	21	Nos.	INR		0.00	INR Zero Only
13	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-fill etc. as required.	80	Mtrs.	INR		0.00	INR Zero Only
14	With 3 mtrs GI pipes having outer pipe dia of 50mm having 80-200 micron galvanising inner pipe dia of 25mm having 200-259 micron galvanizing, connection terminal dia of 12mm in nominal soil with 50 KG (two bag) back filling bentonite compound UL listed and confirm to relevant international / indian standard around electrode upto ground level.	3	Nos	INR		0.00	INR Zero Only
15	Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. 32A TP&N	6	Nos.	INR		0.00	INR Zero Only
16	Supplying and drawing following sizes of FRLS PVC insulated copper conductor , single core cable in the existing surface/ recessed steel / PVC conduit as required 2X6 sqmm	180	Mtrs.	INR		0.00	INR Zero Only
17	Providing and fixing of LED Bulb 12 W	27	Nos.	INR		0.00	INR Zero Only
18	Providing and fixing of LED Tube Light 20 W	16	Nos.	INR		0.00	INR Zero Only
19	Total Impact of GST for the purpose of CTC	1.000	Nos	INR	0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					