

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Project Engineer (E&M), Ashok OCP, Piparwar Area

Name of the Work / Contract No:	Erection of 33KV OHTL both feeder CHP & Mines from existing OHTL to upcoming site of ppr under ground sub-station under Ashok OCP. (Route Length 800M/Each Feeder)	NIT No. : PO(AK)/PE(EnM)/e-NIT/25-26/40				
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (With taxes) in Rs. P	BASIC RATE (Without taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement :3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc. as required.	66	Each	7424.56		0.00	INR Zero Only
2	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required.	2258.39	Kg	227.74		0.00	INR Zero Only
3	Making & Fixing of Single pole complete(3 no conductor bracket & 1 no sky wire bracket) of 33Kv over head line etc as required.	17	Set	4366.83		0.00	INR Zero Only
4	Making of two length of channel iron 100mm x 50mm x 9.56 kg/m double pole cross arm for three wire 33 kv over head line conductors complete with through bolts and nuts for clamping to poles 50mm x 6mm,including drilling holes for insulator fittings bolts and nuts etc as required.	40	Set	3665.73		0.00	INR Zero Only
5	Making & erection of a set of cross bracing frame work for 33 kv over head line double pole structure having 4 nos fabricated out of 65 mmx 65mmx6mm angle iron to form a rectangle of minimum size 2400mm width x 2800mm height complete with 50mmx 6mm MS flat iron clamps bolts & nuts including drilling holes as required.	20	Set	5163.70		0.00	INR Zero Only
6	Supplying and erection of a set of three 11 KV disc insulator for 33 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	195	Set	2796.60		0.00	INR Zero Only
7	Supply of 7/10 SWG GI wire. (Note- Rate taken as per 6 swg GI wire from CPWD 2022 for per Kg)	1265.33	Kg	85.49		0.00	INR Zero Only
8	Erection of G.I. Wire No. 7/10 SWG including binding etc. as required.(Note- Rate taken as per 8 swg GI wire from CCL 2024 for per Kg)	1265.33	Kg	34.22		0.00	INR Zero Only
9	Supplying and erection of galvanised stay set for 33 KV over head lines complete with 19/ 20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm thick, thimble, stay clamps, turn buckle (20 mm X 600 mm) , 7/ 4.00 mm dia GI stay wire and 33 KV strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	37	Each	5188.46		0.00	INR Zero Only
10	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words			INR Zero Only				