

Item Rate BoQ

Tender Inviting Authority:	P.E, (E&M)/Kedia Washery.						
Name of the Work / Contract No:	Laying of cable for power supply to BRO weighbridge and 304B/Conv. unit and light fixing at different location of main plant at Kedia Wshery. NIT No-PO/KWE-Tender/25-26/ date:-						
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(In Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Laying of one number PVC sheathed/XLPE power cable of 1.1KV/grade of 95sq. mm and 185sq. Mm size direct in ground including excavation and refilling the trench etc. as required.	200,000	mtr.			0.00	INR Zero Only
2	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of 185sq. Mm and upto 400sq. Mm size direct in ground including excavation sand cuishining protective covering and refilling the trench etc. as required.	200,000	mtr.			0.00	INR Zero Only
3	Dismantling of Old and Damaged cable Un-skilled manpower(04 Nos.)	10,000	shift			0.00	INR Zero Only
4	Sem-Skilled-manpower	10,000	shift			0.00	INR Zero Only
5	Skilled- manpower-	10,000	shift			0.00	INR Zero Only
6	Supplying, installing, testing and commisioning of 63A TPN tap off box made 1.6mm thick sheet enclosure duly painted with powder coating on existing rising mains complete with TPN disconnector FSU and HRC fuses, connection, earthings etc. as required.	1,000	No.			0.00	INR Zero Only
7	Supply and fixing of street light 200W	20,000	Nos.			0.00	INR Zero Only
8	Bush cutting and tree trimming, Un-Skilled- Manpower(04nos.)	8,000	shift			0.00	INR Zero Only
9	Semi-Skilled- Manpower.	8,000	shift			0.00	INR Zero Only
10	Supplying and fixing of 32mm diaX 2.00mtrs long G. I. pipe (medium class) bracket for mounting of flourscent/HPMV/HPSV street light fitting on pole including bending the pipe to the required shape 2nos. 40X3mm flat iron clamps with nutsbolts and washer painting the flat iron with primer and finish paint etc. as required.	20,000	Nos.			0.00	INR Zero Only
11	Wiring for circuit/sub main wiring along with earth wire with the 2X2.5+1X2.5sq. Mm earth wire of FRLS PVC insulated copper conductor single core cable in surfac/recessed medium class PVC conduit as required.	90,000	mtr.			0.00	INR Zero Only
12	Total impact of GST for the purpose of CTC	1.00	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					