

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff officer (E&amp;M), NK Area, CCL

Name of the Work / Contract No:	Dismantling and Erection of damaged electrical poles of 3.3 kV OH Line from Dakra Substation to Feeder Breaker under Dakra Project, NK Area	NIT No. GM (NK)/EnM/eNIT/2025-26/123; dated 05.12.2025.			
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Dismantling of pole / street light standard /strut embedded in cement concrete foundation etc. as required.	9.00	Nos		0.00	INR Zero Only
2	Dismantling of over head lines comprising of copper / aluminium over head conductor, G.I. wire, cross arms, insulators etc as required	916.00	kg		0.00	INR Zero Only
3	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required. Above 10.00 Metre and upto 12.00 Metre.	12.00	Nos		0.00	INR Zero Only
4	Erection of all aluminum conductor of 7/3.40 mm to 7/4.00 mm diameter and above including binding etc as required.	754.00	kg		0.00	INR Zero Only

5	Supplying and erection of stay set complete (galvanized) with 19/ 20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, bow tightener, 7/ 3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size ) foundation including excavation and refilling etc. as required.	23.00	Nos		0.00	INR Zero Only
6	Supply and erection of 11 KV pin insulator complete with large steel head G.I pin, nuts, washers etc as required.	27.00	Nos		0.00	INR Zero Only
7	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanized insulator fittings, ball and socket type and complete with galvanized strain clamps, bolts, nuts, washers etc. as required.	18.00	Nos		0.00	INR Zero Only
8	Supplying of channel iron 75 mm x 40 mm x 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins and painting with primer and finished paint as required.	6.00	Set		0.00	INR Zero Only
9	Supply of 8 / 6 SWG G.I. wire	312.00	kg		0.00	INR Zero Only
10	Erection of G.I. wire 8 SWG including binding etc as required.	289.00	kg		0.00	INR Zero Only
11	Erection of cradle Guard as required.	120.00	Nos		0.00	INR Zero Only
12	Erection of angle iron / channel iron cross arm on wood / RCC / PCC/ Steel Tubular/ rail pole etc. as required.	8.00	Set		0.00	INR Zero Only
13	Earthing with copper earth plate 600 mm x 600 mm x 3 mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 mtrs long etc etc. with charcoal/ coke and salt as required.	5.00	Set		0.00	INR Zero Only
14	Providing and fixing 25 mm x 5 mm G.I. strip on surface or in recess for loop earthing as required.	75.00	Mtr		0.00	INR Zero Only
15	Supplying and erection of three piece nonlinear resistor type lightning arrestor suitable for 3 wire, 11 KV/ 3.3 kV overhead lines with rated voltage 9 KV (rms) with a nominal discharge current rating of 5 KA and complete with galvanized clamping arrangement, G.I. bolts, nuts, washers etc as required.	3.00	Set		0.00	INR Zero Only
16	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					0.00	INR Zero Only
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>				

