

Tender Inviting Authority: Project Engineer(E&M), Gidi-C Colliery,Agada Area, CCL.						
Name of the Work / Contract No:		Supply and installation of Air Breaker Switch/GOAB at different locations of Gidi-C Colliery Under Argada Area.		NIT No:PE(E&M)/GDC/eNIT/25-26/16		Dated: 08.12.2025
-		Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	0.00	0.00	0.00
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Supply and fixing of 11 KV grade Air break switch 630 Amp Horizontal type	14	Nos		0.00	INR Zero Only
2	Supplying and erection of bowstay set complete (galvanised) with 19/20mm diax1.8 metres long stayrod,anchor plate of size 45cmx45cmx7.5mm, thimble, stayclamps, turnbuckle(20mmx60cm), 7/4.00mmdia G.I.stay wire and strain insulator etc incement concrete 1:3:6 (1cement:3coarse sand:6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and also with 0.6m long brace of size 50mm X 50mmx6mm angle iron with 50mm dia pulley fixed at one end of the brace as required.	14	Set		0.00	INR Zero Only
3	Supplying of two lengths of channel iron 75mmx40mmx6mm (7.14kgper metre) double pole cross arm for three wire 11KV overhead line conductors complete with through bolts and nuts for clamping to the poles, 50mmx6 mm M.S. flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulatorpins/fittings, bolts, nuts and washer setc(as per drawing)and painting with primer and finish paint as required.	28	Set		0.00	INR Zero Only
4	Supplying and erection of a set of cross bracing FRLSame work for 11KV over headline double pole structure having four members fabricated out of 50mmx 50mmx6mm angle iron to form a rectangle of minimum size 1400mmX widthx2500mm height, complete with 50mmx6mm M.S. flat iron clamps, bolts and nuts including drilling holes for insulator pins, bolts and nuts etc (as per drawing) and painting with primer and finish paint as required.	14	Set		0.00	INR Zero Only
5	Total impact of GST for the purpose of CTC	1	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				