

Tender Inviting Authority: Project Engineer(EnM),Urimari OCP, Barka-Sayal Area, CCL.						
Name of the Work / Contract No:	Erection, dismantling and strenghtening of poles , conductor and earth wire LT 440V OH line at Tipla siding under Urimari OCP.			NIT No. : PE(EnM)/Urimari/e Tender/25-26/36		Dated: 09/12/2025
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	0.00	0.00	0.00
<p align="center">PRICE SCHEDULE</p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of metallic pole of above 10.00 Mtr and upto 12.00 Mtr length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	14.00	No.		0.00	INR Zero Only
2	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10 mm diameter including binding etc. as required	827.40	Kg		0.00	INR Zero Only
3	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, bow tightener, 7/ 4.00 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required	7.00	Each		0.00	INR Zero Only
4	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	8.00	Set.		0.00	INR Zero Only
5	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required .	28.00	Set.		0.00	INR Zero Only
6	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required .	14.00	Set.		0.00	INR Zero Only
7	Supply of 08 SWG GI Wire	91.70	Kg		0.00	INR Zero Only
8	Erection of G.I. Wire No. 8 SWG including binding etc. as required.	91.70	Kg		0.00	INR Zero Only
9	Dismantling of over head lines comprising of copper/ aluminium over head conductor, G.I. wire, cross arms, insulators etc. as required	477.68	Kg		0.00	INR Zero Only
10	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required	12.00	No.		0.00	INR Zero Only
11	Loading and Unloading of Pole and OH material	1.00	No.		0.00	INR Zero Only
12	Total impact of GST for the purpose of CTC	1.000	No.	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				