

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:

Repairing of HT (3.3kV) and LT (440V) Control Switchgear of 750 kVA, 3.3 kV/440V TSU, SL No. 9361, Make Meditron installed at IR Feeder Breaker of KDH OCP, NK Area

NIT No. GM (NK)/EnM/eNIT/2025-26/125; dated 10.12.2025.

Category of Services (To Be Selected by Department)

Category of Bidder (To Be Selected by Bidder)

ITC Available

Works Contract

Bidder's Status (Mandatory)

Total GST(in Rs.)

GST to be Paid By Bidder (in Rs.)

GST to be Paid By CIL/Subsidiary (in Rs.)

Name of the Bidder/ Bidding Firm / Company :

Select

0.00

0.00

0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Providing and fixing of Numerical Earth Leakage Relay Current setting 20mA to 12 Amp in step of 1mA, Aux Supply 24-265V AC/DC	2.00	Nos		0.00	INR Zero Only
2	Providing and fixing of Inverse Time Numerical Current Relay 1A/5A Site Selectable Range 250 mA to 200 Amp (5% to 4000%), 50 Hz, Aux Supply 80-265V AC/DC	2.00	Nos		0.00	INR Zero Only
3	Providing and fixing of CBCT of assored size	1.00	Nos		0.00	INR Zero Only
4	Providing and fixing of Current Transformer for LT side ACB control panel, Ratio 1250/5A	3.00	Nos		0.00	INR Zero Only
5	Providing and fixing of Potential Transformer Resin Cast, 750VA, 3 Ph, 3.3 kV/110V	1.00	Nos		0.00	INR Zero Only
6	Providing and fixing of breather with Silica gel of aluminium dia container Poly Carbonate power coated with Flange Mounted with silica gel blue 2 KG capacity.	1.00	Nos		0.00	INR Zero Only
7	Wiring with materials including PVC wires, lugs, ferrules, Nut, Bolt with washer etc.	1.00	Nos		0.00	INR Zero Only
8	Complete denting, painting and cleaning of transformer body and HT and LT Panel with one coat primer and two coat color enamel paint.	1.00	Job		0.00	INR Zero Only
9	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				