Validate	Print Help	Item Rate BoQ				
Tender Inviting Author	ority: Project Engineer(EnM),Uri	imari OCP, Barka-Sayal Area, CCL.				
Name of the Work /		al shutdown rule/shock treatment chart, SLD, Electrical hazard ds and shock safe insulating mat at 33KV and 11KV substations	NIT No. : PE			

Category of Bidder ( To Be Selected by Bidder) Category of Services (To Be Selected by Department)

GST to be Paid By Bidder (in Rs.) Works Contract ITC Available Total GST(in Rs.) GST to be Paid By CIL/Subsidiary (in Rs.) Bidder's Status (Mandatory) Name of the Bidder/ Bidding Firm / Company : 0.00 0.00 0.00

NIT No. : PE(EnM)/Urimari/e Tender/25-26/38

Dated: 11/12/2025

## PRICE SCHEDULE

JMBER#	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SI. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Part-A Manufacturing, supplying and fixing retro reflective overhead signageboards made up of 2 mm thick aluminium sheet, face to be fullycovered with high intensity and encapsulated lens type heat activatedretor reflective sheeting conforming to type - Ill of ASTM-D-4956-01as approved by Engineer-in-charge_letters, borders etc. as per IRC: 67-2001 in silver white with blue colour back ground and with highintensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming toclass I of ASTM-D-4956-01 and fixing the same to the plate ofstructural frame work by means of suitable sized aluminium alloys_rivets or bolts & nuts @ 300 mm centre to centre all along theperiphery as well as in two vertical rows along with thet resistantmeasures, including the cost of painting with two or more coats ofepoxy paint in grey colour on the back side of aluminium sheetincluding appropriate priming coat. The rate includes the cost ofrounding off the corners, lowering down the structural frame workfrom the gantry, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer-in-charge_(Structural frame work including M.S.plate to be providedseparately. Rectangular area of the sheet only shall be measured for payment)	9.00	Sqm		0.00	INR Zero Only
2	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	381.95	Кд		0.00	INR Zero Only
3	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, iic making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall	18.80	Mtr		0.00	INR Zero Only
4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sogm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	1.20	Cum		0.00	INR Zero Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	1.45	Cum		0.00	INR Zero Only
6	Part B- Providing Shock Safe Insulating Mat suitable for 33/11 KV;Colour Black;Size 1 mtr x 2 Mtr x 12mm	18.00	No.		0.00	) INR Zero Only
7	Adhesive for pasting Insulating Mat	18.00	Ltr			INR Zero Only
8	Part C- Contractor Profit	1.00	No.		0.00	NR Zero Only
9	Total impact of GST for the purpose of CTC	1.000	No.	0.00	0.00	INR Zero Only
n Figures					0.00	INR Zero Only
I Rate in Wo	  rds			li li	NR Zero Only	

9