

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL

Name of the Work / Contract No:

Work of "Diversion of 11 KV JBVNL overhead line with DTR 1 X 25 kva for mines extension near Pannatand tola village under Magadh OCP,M-S Area."

NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/25-26/55; Dated:- 06.12.2025.

Category of Services (To Be Selected by Department)

Category of Bidder (To Be Selected by Bidder)

ITC Available

Works Contract

Bidder's Status (Mandatory)

Total GST(in Rs.)

GST to be Paid By Bidder (in Rs.)

GST to be Paid By CIL/Subsidiary (in Rs.)

Name of the Bidder/ Bidding Firm / Company :

Select

0.00

0.00

0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Dismantling of pole/ street light standard/ strut embedded in brick ballast foundation etc. as required.	65	Nos		0.00	INR Zero Only
2	Erection of metallic pole of length above 10mtr and upto 12 mtr in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	25	Nos		0.00	INR Zero Only
3	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required.	355	Kg		0.00	INR Zero Only
4	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	4	Set		0.00	INR Zero Only
5	Erection of angle Iron/channel iron cross arm on wood/RCC/PCC/steel tubular or Rail pole for 4 wire system.	4	Set		0.00	INR Zero Only
6	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) pole top bracket/ cross arm for single 11 KV over head line conductor complete with 50 mm X 6mm flat iron clamp, bolts, nuts and washers including drilling holes for insulator pins, bolts and nuts etc and painting with primer and finish paint as required	17	Set		0.00	INR Zero Only
7	Erection of pole top cross arm on steel tubular/ rail/ PCC pole for 11 KV	17	Set		0.00	INR Zero Only
8	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) V shape cross arm for two 11 KV over head line conductors complete with 50 mm X 6mm M.S. flat iron clamps, bolts and nuts including drilling holes for insulator pins, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required	17	Set		0.00	INR Zero Only
9	Erection of pole V shape two wire, angle iron/ channel iron, cross arm on steel tubular/ rail/ PCC pole for 11KV	17	Set		0.00	INR Zero Only
10	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	24	Set		0.00	INR Zero Only
11	Supplying and erection of 11 KV pin insulator complete with large steel head G.I.	51	Set		0.00	INR Zero Only
12	Supplying and erection of galvanised stay set for 11 KV over head lines complete with 19/ 20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm thick, thimble, stay clamps, turn buckle (20 mm X 600 mm), 7/ 4.00 mm dia G.I. stay wire and 11 KV strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required	7	Set		0.00	INR Zero Only
13	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. (but without charcoal/ coke and salt) as required.with charcoal/coke and salt as required.for shifting of Transformer and Re installation	2	Nos		0.00	INR Zero Only
14	Providing and fixing 6 SWG dia GI wire on surface or in recess for loop earthing as required	25	Mtr		0.00	INR Zero Only
15	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words				INR Zero Only		