

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL						
Name of the Work / Contract No:	Work of "Reconstruction of damaged masonry covers,measurement and installation of noting plates for earthpits,and painting services for existing masonry covers associated with weighbridges,diesel generators and metal tubular poles under magadh OCP,M-S Area."			NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/25-26/58; Dated:- 10.12.2025.		
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
SL No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Providing Salt to improve soil condition and efficiency of the earthing system	140	KG		0.00	INR Zero Only
2	Providing 600 mm X 600 mm X 6 mm thick G.I. plate.For earthpit value noting in Generators and weighbridges	25	Each		0.00	INR Zero Only
3	Finishing walls with water proofing cement paint of required shade complete.(0.40 X 0.40)X5X142)=113.6 SQ M +(0.36 X 142)=51.12=164.72 SQM	164.72	sqm		0.00	INR Zero Only
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work(0.40 X 0.40)X5X142)=113.6 SQ M +(0.36 X 142)=51.12=164.72 SQM	164.72	sqm		0.00	INR Zero Only
5	Providingand fixing 25mmX5mm G.I.strip in 40mm dia G.I.pipe from earth electrode including connection with G.I. nut,bolt,spring,washer excavation and re-filling etc.as required.	55	Metre		0.00	INR Zero Only
6	Providing and fixing 4.00 mm dia copperwire on surface or in recess for loop earthing along with existing surface/recessed conduit/submain wiring/cable as required.for running weighbridges internal earth continuity wire	195	Metre		0.00	INR Zero Only
7	Providing and fixing earth bus of 50mmX5mm copper strip on surface for connections etc.as required.	20	Metre		0.00	INR Zero Only
8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	20	KG		0.00	INR Zero Only
9	Making of masonry enclosure of Earthpits	30	Nos		0.00	INR Zero Only
10	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words				INR Zero Only		