

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL.

Name of the Work / Contract No:

Work of "Extension of overhead line for lighting arrangement in coal stock 59,60,62, and 64 including transporting road to 44 number coal stock approx route length 1600 metres under Magadh OCP, M-S Area."

NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/25-26/60; Dated:- 11.12.2025.

Category of Services (To Be Selected by Department)

Category of Bidder (To Be Selected by Bidder)

ITC Available

Works Contract

Bidder's Status (Mandatory)

Total GST(in Rs.)

GST to be Paid By Bidder (in Rs.)

GST to be Paid By CIL/Subsidiary (in Rs.)

Name of the Bidder/ Bidding Firm / Company :

Select

0.00

0.00

0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
SL No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of metallic pole of length above 10mtr and upto 12 mtr in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	46	Nos		0.00	INR Zero Only
2	Erection of ACSR conductor of 7/2.11 mm to 7/3.00 mm diameter including binding etc. as required.	621	Kg		0.00	INR Zero Only
3	Cutting of 6" dia damaged or spare pipe in suitable 3 meter size by gas/electric welding M/C, (6X51.75 =310.5) for 6 meter 6" inch dia pipe jointing.For heightning of pole near pole crossing.	310.5	CM		0.00	INR Zero Only
4	Welding of 6" dia pipe to pipe for jointing by gas/electric welding M/C, (6x51.75 =310.5) for 6 meter 6" inch dia pipe jointing.For heightning of pole near pole crossing.	310.5	CM		0.00	INR Zero Only
5	Erection of angle Iron/channel iron cross arm on wood/RCC/PCC/steel tubular or Rail pole for 4 wire system.	35	Set		0.00	INR Zero Only
6	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	35	Set		0.00	INR Zero Only
7	Supplying of channel iron 75mmX40mmX6mm (7.14kgpermetre) cross arm for 2 wire over head line complete with clamps,bolts,nuts and washer etc including drilling of holes for insulator pins etc (as per drawing)and painting with primer and finished paint as required.	35	Set		0.00	INR Zero Only
8	Erection of angle Iron/channel iron cross arm on wood/RCC/PCC/steel tubular or Rail pole for 2 wire system.	35	Set		0.00	INR Zero Only
9	Supplying and erection of stay set complete (galvanised) with 19/ 20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, bow tightener, 7/ 3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	18	Set		0.00	INR Zero Only
10	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required .	96	Set		0.00	INR Zero Only
11	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required.	88	Set		0.00	INR Zero Only
12	Erection of G.I wire no-6/8 SWG including binding etc.as required for cage cradle and crosslacing.	4	span		0.00	INR Zero Only
13	Providing of 25 sq mm 4 core isi marked,upto 1.1 kv grade Aluminium armouredcable for laying service wire for weighbbridges from Generator and Overhead line.	22	mtr		0.00	INR Zero Only
14	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required	22	Mtr		0.00	INR Zero Only
15	Supplying of 300 watt LED flood light with 2 years warranty	35	Nos		0.00	INR Zero Only
16	Supplying and drawing following sizes of FRLS PVC insulated copper conductor single core cable in the existing surface / recessed steel / PVC conduit as required.2x 1.5 sq. mm.For service wire of lights	70	mtr		0.00	INR Zero Only
17	Providing and fixing 100 A rating and breaking capacity and 4 pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections. etc. as required.	2	Each		0.00	INR Zero Only
18	Providing and fixing 100 A rating and breaking capacity and 4 pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections. etc. as required.	2	Nos		0.00	INR Zero Only
19	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	