

Tender Inviting Authority: Project Engineer (E&M), Govindpur Project							
Name of the Work / Contract No:	Comprehensive Annual Maintenance Contract (CAMC) of electrical repairing / re-wiring of some electrical points with changing of switches and switch boards etc. of different colonies i.e. ('A' Type = 16 Quarters, 'B' Type = 158 Quarters, 'C' Type = 30 Quarters, 'D' Type = 04 Quarters and 'MQ' Type = 540 Quarters) of township including service buildings, dispensary and club under Govindpur Project, Kathara Area for a period of Two (2) Years.				NIT No. : PE(E&M)/GVP(U/G)/E-Tender/2025-26/ 10 Date- 12.12.2025		
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (In %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company		Select	18	0.00	0.00	0.00	
<p align="center"><b>PRICE SCHEDULE</b></p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )</p>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Wiring for light point /fan point/exhaust fan point / call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduct, with piano type switch, phenolic laminated sheet, suitable size M.S box and earthing the point with 1.5Sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group 'C'	312	POINT			0.00	INR Zero Only
1.02	Supplying and fixing following piano type switch / socket on the existing switch box / cover including connections etc. as required. 1). 5/6 Amps Switch	1560	NOS.			0.00	INR Zero Only
1.03	2). 3 Pin 5/6 Amps Socket out let	780	NOS.			0.00	INR Zero Only
1.04	3). 15/16 Amps Switch	468	NOS.			0.00	INR Zero Only
1.05	4). 6 Pin 15/16 Amps Socket out let	468	NOS.			0.00	INR Zero Only
1.06	Supplying and fixing metal box of 150mm X 75mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 amps socket outlet and 5/6 amps piano type switch, connection, painting etc. as required. (For light plugs to be used in non residential buildings).	312	NOS.			0.00	INR Zero Only
1.07	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	312	NOS.			0.00	INR Zero Only
1.08	Supplying and fixing followings way, single pole neutral, sheet steel, MCB distribution board, 240 volts, on surface / recess, completed with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required (But without MCB/RCCB/Isolator). 1) 2/4 way & 8 way Double Door	156	NOS.			0.00	INR Zero Only
1.09	Supplying and fixing call bell/ buzzer suitable for single phase, 230 V, complete as required.	156	NOS.			0.00	INR Zero Only

1.10	Supplying and fixing of brass batten / angle holder including connection etc. as required.	780	NOS.			0.00	INR Zero Only
1.11	Supplying and fixing 5 Amps to 32 Amps rating, 240/415 volts, 'C' curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. I) Single pole and neutral.	312	NOS.			0.00	INR Zero Only
1.12	Wiring for circuit / sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC consult. I). 2 X 4 sq.mm + 1 X 4 sq.mm earth wire	936	MTRS.			0.00	INR Zero Only
1.13	Wiring for circuit / sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC consult. I). 2 X 2.5 sq.mm + 1 X 2.5 sq.mm earth wire	1872	MTRS.			0.00	INR Zero Only
1.14	Providing and fixing of Copper Wire Twin Core (7/20) for service line connection.	780	MTRS.			0.00	INR Zero Only
1.15	Providing and fixing following capacity TP&N disconnecter fuse switch unit inside the exiting panel board with ISI marked HRC fuses including drilling holes in cubicle, making, connections etc. as required. 32Amp TP & N	156	NOS.			0.00	INR Zero Only
1.16	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required (Size-25mm).	780	MTRS.			0.00	INR Zero Only
1.17	Supplying and fixing of 3 pin, 5A ceiling rose on the existing junction box / wooden block including connection etc. as required.	468	NOS.			0.00	INR Zero Only
2	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos.		0.00	0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>					