

Validate		Print		Help			
Tender Inviting Authority:		SO(E&M)/ H					
Name of the Work / Contract No:		Fresh wiring of Security room ,gate entry room, motor-cycle stand, lab room and watch tower of RRST/N Hazaribagh Area					
		Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.00
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required Group A	128	No			0.00	INR Zero Only
2	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required	6	No			0.00	INR Zero Only
3	Supplying and fixing 3 pin, 5 amp ceiling rose on the existing junction box/ wooden block including connection etc as required.	6	No			0.00	INR Zero Only
4	Supplying and fixing brass batten/ angle holder including connection etc. as required.	28	No			0.00	INR Zero Only
5	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required 5/6 amps switch	60	No			0.00	INR Zero Only
6	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required 15/16 amp switch	24	No			0.00	INR Zero Only
7	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required 5/6 amp socket outlet	40	No			0.00	INR Zero Only
8	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required 6 pin 15/16 amp socket outlet	16	No			0.00	INR Zero Only
9	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	389	Mtr			0.00	INR Zero Only
10	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required 2 X 4 sq. mm + 1 X 4 sq. mm earth wire (service Wire)	282	Mtr			0.00	INR Zero Only
12	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc.as required. (But without MCB/RCCB/Isolator) 6 way , Double door	3	No			0.00	INR Zero Only
13	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required SP and neutral	18	No			0.00	INR Zero Only
14	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including	6	No			0.00	INR Zero Only
15	Providing and fixing 4.00 mm diacopper wire on surface or in recess for loop earthing	120	Mtr			0.00	INR Zero Only
16	Supply and fixing of 18 W Led Bulb	15	No			0.00	INR Zero Only
17	Supplying, installing, testing and commissioning of following capacity TPN tap off box made of 1.6mm thick sheet steel enclosure duly painted with powder coating on existing rising mains complete with TPN disconnector FSU and HRC fuses, connections, earthing etc. as required.	3	No			0.00	INR Zero Only
18	Total impact of GST for the purpose of CTC	1.00	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					