

**Item Rate BoQ**

Tender Inviting Authority : Staff Officer (Civil), Magadh-Sanghmitra Area.

Name of the Work / Construction of 500 mtrs. PCC road in Raham Village of Magadh-Sanghmitra Area under CSR. (e NIT No. 68 of 2025-26)  
Contract No:

	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Excavation in Soil using Hydraulic Excavator and Tipppers with Disposal upto 1000 metres. Excavation for roadwork in soil with hydraulic excavator including cutting and loading in tipppers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location within all lifts and lead upto 1000m.	290.70	cum			0.00	INR Zero Only
2	Plant Mix Method (Construction of granular sub-base by providing close graded Materials, mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401). for grading - II material	145.35	cum			0.00	INR Zero Only
3	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	239.06	cum			0.00	INR Zero Only
4	Construction of sub-grade and earthen shoulders (Construction of sub-grade and earthen shoulders with approved material obtained from borrow pits with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table No. 300-2.	57.38	cum			0.00	INR Zero Only
5	Excavation for Structures (Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material.) Ordinary soil Mechanical Means Depth upto 3 m	170.10	cum			0.00	INR Zero Only
6	Sand Filling in Foundation Trenches as per Drawing & Technical Specification	6.98	cum			0.00	INR Zero Only
7	Plain cement concrete 1:3:6 nominal mix in foundation with crushed stone aggregate 40 mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days.	16.20	cum			0.00	INR Zero Only
8	Stone Masonry Work in Cement Mortar 1:3 in Foundation complete as per Drawing and Technical Specifications. Random Rubble Masonry	48.15	cum			0.00	INR Zero Only
9	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 600 mm dia RCC pipes.	10.00	Meter			0.00	INR Zero Only

10	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					