

Tender Inviting Authority: PROJECT OFFICER REGIONAL REPAIR SHOP KATHARA							
Name of the Bidder / Contract No:	Day-to-Day Maintenance of Main 11kV, 6.6kV, and 440V OHT lines and Painting and Strengthening of Electric Poles of R.R Shop, Jarangdh						
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		GST Registered Bidder(under Regular Scheme)	18	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
2.01	Maintenance of Main 11 KV, 6.6 KV & 440 Volt distribution Overhead line						
2.02	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	6.00	Nos			0.00	INR Zero Only
2.03	Supplying and erection of 11 KV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required.	6.00	Nos.			0.00	INR Zero Only
2.04	Supplying of PCC/RCC pole and upto 9 mtr long	4.00	Nos.			0.00	INR Zero Only
2.05	Erection of RCC/ PCC pole of following length in brick ballast and ramming the foundation, finishing with 150mm thick cement concrete (1:3:6) layer on top with including excavation and refilling etc as required. (Above 8.0 metre and upto 11.0 metre)	4.00	Nos			0.00	INR Zero Only
2.06	Supplying and erection of bow stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm x 7.5 mm, thimble, stay clamps, turn buckle ( 20 mm X 60 cm ), 7/ 3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size ) foundation including excavation and refilling and also with 0.6 m long brace of size 50 mm X 50 mm X 6 mm angle iron with 50 mm dia pulley fixed at one end of the brace as required..	3.00	Nos			0.00	INR Zero Only
2.07	Erection of LVIMV shackle/pin insulator etc. as required.	40.00	Nos.			0.00	INR Zero Only
2.08	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required	60.00	Nos			0.00	INR Zero Only
2.09	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required	20.00	Nos			0.00	INR Zero Only
2.1	Erection of double pole 3 wire cross arm for 11KV/ 22KV/ 33 KV over head lines as required.	1.00	Nos			0.00	INR Zero Only
2.11	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) double pole cross arm for three wire 11KV over head line conductors complete with through bolts and nuts for clamping to the poles, 50 mm X 6 mm M.S. flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/ fittings, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required.	1.00	Nos.			0.00	INR Zero Only
2.12	Supplying and erection of a set of cross bracing FRLSame work for 11 KV over head line double pole structure having four members fabricated out of 50 mm X 50 mm X 6 mm angle iron to form a rectangle of minimum size 1400 mm width X 2500 mm height , complete with 50 mm X 6mm M.S. flat iron clamps, bolts and nuts including drilling holes for insulator pins, bolts and nuts etc (as per drawing) and painting with primer and finish paint as required.	1.00	Nos.			0.00	INR Zero Only
2.13	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) pole top bracket/ cross arm for single 11 KV over head line conductor complete with 50 mm X 6mm flat iron clamp, bolts, nuts and washers including drilling holes for insulator pins, bolts and nuts etc and painting with primer and finish paint as required.	1.00	Nos.			0.00	INR Zero Only
2.14	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for two 11 KV over head line conductors complete with 50 mm X 50 mm X 6 mm (angle iron bracket welded to the channel iron and complete with 50 mm X 6mm M.S. flat iron clamps, bolts and nuts including drilling holes for insulator pins, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required.	1.00	Nos.			0.00	INR Zero Only
2.15	Erection of angle iron/ channel iron cross arm on wood/ RCC/ PCC/ steel tubular/ rail pole etc. as required.	10.00	Nos			0.00	INR Zero Only
2.16	M.S Nut & bolts as per required sizes	10.00	Kgs			0.00	INR Zero Only
2.17	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	4.00	Nos.			0.00	INR Zero Only
2.18	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	2.00	Nos.			0.00	INR Zero Only
2.19	Erection of ACSR conductor of 7/2.11 mm to 7/3.00 mm diameter including binding etc. as required.	394.00	Kgs			0.00	INR Zero Only
2.2	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10 mm diameter including binding etc. as required.	600.00	Kgs			0.00	INR Zero Only
2.21	Erection of all aluminium conductor of 7/3.40 mm to 7/4.00 mm diameter and above including binding etc. as required.	250.00	Kgs			0.00	INR Zero Only
2.22	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required.	5.00	Nos			0.00	INR Zero Only
2.23	Dismantling of over head lines comprising of copper/ aluminium over head conductor, Cl. wire, cross arms, insulators etc. as required.	360.00	Kgs			0.00	INR Zero Only
2.24	Craedling with 8 SWG with all Accessories	2.00	Nos.			0.00	INR Zero Only
2.25	Cutting and trimming of Trees and bushes along 11kv, 6.6kv ,440v OH Lines and around transformer area						
2.26	Cutting and trimming of trees branches, Bushes and shrubs along 11kv,6.6kv and 440v overhead lines of Colony no 1,2 &2 and workshop of RR shop Jarangdh.	45.00	Days			0.00	INR Zero Only
2.27	Strengthening and painting of old electric poles of 440V OH Lines of colonies of RR Shop						
2.28	Providing and laying in position cement concrete 1:2:4 (1 Cement: 2 Coarse sand : 4 Graded stone agg, 20mm nominal size) in foundation of pump, DG Set etc. including farm work. as required. (0.75 x 0.75 x 1m) x 18 nos. of poles = 10.125 Cum	10.13	Cum			0.00	INR Zero Only
2.29	Painting of pole with bracket clamp etc	113.00	Nos.			0.00	INR Zero Only
2.3	Painting of synthetic enamel paint of approved brand and manufacture to give an even shade (yellow colour) two or more coats on new work (for numbering). 113 Poles x 1.5 sq.m = 169.5 sq.m	169.50	SQM			0.00	INR Zero Only
3	Total impact of GST for the purpose of CTC	1.000	Nos			0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					