

Tender Inviting Authority: Staff officer (E&M), Amrapali- Chandragupta Area, CCL						
Name of the Work / Contract No:	Supply and fixing of SPD in weighbridges and checkpost installed at Amrapali OCP			NIT No: G.M.(A-C)/S.O.(E&M)/e-NIT/25-26/25 ; Dated: 18.12.2025		
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
<p align="center"><b>PRICE SCHEDULE</b></p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit alongwith 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required	92.000	Mtr.		0.00	INR Zero Only
2	Sungle core 35 sqmm flexible copper cable, 1.1 KV grade ISI marked. ( 19 X 3 Mtr)	69.000	Mtr.		0.00	INR Zero Only
3	Surge protection device three phase and netural, 3P+N, 440 Volts, Class I + Class II combination ( Volatge switching and voltage limiting) having preferred values of impluse discahrge current for class I ( in KA) 25, prefereed values of nominal discharge current for class II test in (KA) 15 and prefred values of voltage protection level up (in KV) 1.5, CE certification, governing specification 'IS 16463 (part II)' 2016 or ICE 61643-11:2011"	23.00	Each		0.00	INR Zero Only

4	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator). 6 way (4 + 18), Double door	23.00	Each		0.00	INR Zero Only
5	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required .	23.00	Set		0.00	INR Zero Only
6	Providing and fixing earth bus of 50 mm X 5 mm copper strip on surface for connections etc. as required.	23.00	Mtr.		0.00	INR Zero Only
7	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required. 32 mm	345.00	Mtr.		0.00	INR Zero Only
8	Supplying and laying 25 mm X 5 mm G.I strip at 0.50 metre below ground as strip earth electrode, including connection/terminating with G.I. nut, bolt, spring, washer etc. as required.(Jointing shall be done by overlapping and with 2 sets of G.I. nut bolt & spring washer spaced at 50mm)	276.00	Mtr.		0.00	INR Zero Only
9	<b>Total impact of GST for the purpose of CTC</b>	1.000	Job	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					0.00	INR Zero Only
<b>Quoted Rate in Words</b>					<b>INR Zero Only</b>	