

Item Rate BoQ

ValidatePrintHelp

Tender Inviting Authority:	PE EnM, TSOCp					
Name of the Work / Contract No:	Dismantling and erection of 3.3KV overhead line with providing and installation of 11KV GOAB switch at old quarry of Tapin South OCP under hazaribagh area.					
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(In Rs.)	GST to be Paid By Bidder (In Rs.)	GST to be Paid By CIL/Subsidiary (In Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Dismantling of pole/street light standard/strut embedded in cement concrete foundation etc .as required	4.00	nos			0.00	INR Zero Only
2	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc. as required.	6.00	nos			0.00	INR Zero Only
3	Supplying and erection of stay set complete (galvanised) with 19/ 20 mm dia X 1.8 metres long stay rod- anchor plate of size 45cm X45cmX7.5mm, thimble, stay clamps, bow tightener, 7/3.15mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1cement:3coarse sand:6graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc.as required.	5.00	nos			0.00	INR Zero Only
4	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required.	266.00	kg			0.00	INR Zero Only
5	Dismantling of overhead lines comprising of copper/aluminium overhead conductor, G.I.wire, crossarms, insulators etc.as required.	130.00	kg			0.00	INR Zero Only
6	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over headline complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	5.00	nos			0.00	INR Zero Only
7	Erection of angle iron/channel iron cross arm on wood/RCC/PCC/ steel tubular/rail pole etc.as required	7.00	nos			0.00	INR Zero Only
8	Supplying and erection of 100 mm X 80 mm pin insulator complete with G.I. Spindle and nuts etc. as required	21.00	Nos			0.00	INR Zero Only
9	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	5.00	Nos			0.00	INR Zero Only
10	Erection of cradle guard as required	2.00	Nos			0.00	INR Zero Only
11	Making of cradle guard by supplying 8 SWG GI wire	2.00	Nos			0.00	INR Zero Only
12	providing and fixing of 11KV, 400A grade air break switch	1.00	Nos			0.00	INR Zero Only
13	providing and fixing of 35 sq mm wire for earthing	40.00	mtr			0.00	INR Zero Only
14	Earthing with copper earth plate 600 mm x 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required	2.00	Nos			0.00	INR Zero Only
15	Supply and erection of stay wire (7/3.15 mm dia) for earth continuity (225 Mtr X 0.469 Kg/ Mtrs X 1.05 =110.80 Kg)	110.80	kg			0.00	INR Zero Only
16	Total impact of GST for the purpose of CTC	1.00	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						