

Tender Inviting Authority:	SO(E&M)/ H						
Name of the Work / Contract No:	Maintenance and repairing of 1600 KVA 11KV/3.3KV Power Transformer, NGR Repairing with proper earthing and Shed at main substation of JOCP under Hazaribag Area						
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
<b>PRICE SCHEDULE</b> (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Supply & Fixing of Cost of Off Circuit Tap Changer	1	No			0.00	INR Zero Only
2	Supply & Fixing of Breather Clear view type with out Silica Gel Overall height of silicagel breather (in735mm), Maximum dia of silicagel breather (in 355mm),Compatible connection Pipe size 1"	1	No			0.00	INR Zero Only
3	Supply & Fixing of Copper Flat 38 mm X 5 mm required for 3 phase + 1 netrul connection in 3.3KV side transformers 7 Mtr approx required X 1.712 Kg p/mtr weight =11.98 Kg ( Say 12 kg)	12	Kg			0.00	INR Zero Only
4	Supply & Fixing of Bushing with studs HV 11KV/3.3KV grade	4	No			0.00	INR Zero Only
5	Online Oil filtration of Transformer at site	1344	Ltr			0.00	INR Zero Only
6	Supply & Fixing of Cork Sheet 6mm, 3 Feet X 2 feet	6	No			0.00	INR Zero Only
7	Supply & Fixing of Cast iron valve 1.5 inch	2	No			0.00	INR Zero Only
8	Supply & Fixing of Cable 12 core x 1.5 sq mm, 1.1KV copper un-	80	Mtr			0.00	INR Zero Only
9	Supply & Fixing of C.T 3.3kv CTR 200-100/5+5A	1	No			0.00	INR Zero Only
10	Supply & Fixing of Fail Safe relay	1	No			0.00	INR Zero Only
11	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	1	No			0.00	INR Zero Only
12	Supply & Fixing of Aluminium Unarmoured cable single core1100 voltage grade 35 sq mm	30	Mtr			0.00	INR Zero Only
13	Supply & Fixing of Aluminium tub terminal 35 sq mm	2	No			0.00	INR Zero Only
14	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	375	Kg			0.00	INR Zero Only
15	Total impact of GST for the purpose of CTC	1.00	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						