

Tender Inviting Authority:	Project Engineer (EnM), PEOCP, Hazaribagh Area					
Name of the Work / Contract No:	Repairing and overhauling of (A) Andrew Yule make VCB 3.3 KV, 630Amp sl no-2728 installed at Parej substation secondary control of 3 MVA Power Transformer & (B)Sait Teknik pvt ltd make 3.3KV, 360KW HT Starter sl no-SAHD2732 at Parej OCP under Hazaribag Area.					
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By ClL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder In Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7	8
1	Part (A) Andrew Yule make VCB 3.3 KV, 630Amp sl no-2728 Supply & Fixing of Current transformer, CTR 400/200/5+5,3.3KV grade, epoxy resin cast type	2	No			0.00	INR Zero Only
2	Supply & Fixing of Rectifire Unit with 40AMP current capacity and 110 V DC voltage grade	1	No			0.00	INR Zero Only
3	Supply & Fixing of P.T Fuse 3.3 KV /3Amps rated for PT	3	No			0.00	INR Zero Only
4	Supply & Fixing of Auxillary contact 110V	1	No			0.00	INR Zero Only
5	Supply & Fixing of Series trip Mechanism	1	No			0.00	INR Zero Only
6	Supply & Fixing of Selector Switch 16Amp rated	1	No			0.00	INR Zero Only
7	Supply & Fixing of AMP Meter 0-600 A range, 110V, 4" Sq.mm.size	1	No			0.00	INR Zero Only
8	Supply & Fixing of Volt Meter, 0-15KV range, 110V, 4"Sq. mm. size	1	No			0.00	INR Zero Only
9	Supply & Fixing of Support Insulator dia 75mm length 90mm	2	No			0.00	INR Zero Only
10	Supply & Fixing of Shunt Trip Coil 110V AC/DC grade	1	No			0.00	INR Zero Only
11	Supply & Fixing of Push Button Mushroom type 1NO+1NC	2	No			0.00	INR Zero Only
12	Supply & Fixing of Indicating lamp 110V , AC/DC rated for each phase (R/Y/B)	2	No			0.00	INR Zero Only
13	Wiring with ferruls & Lugs as required materials	1	Job			0.00	INR Zero Only
14	Part (B) Sait Teknik pvt ltd make 3.3KV, 360KW HT Starter sl no-SAHD2732 Supply & Fixing of	1	No			0.00	INR Zero Only
15	RESIN CAST MOULDED CT FOR O L RELAY	1	No			0.00	INR Zero Only
16	Supply & Fixing of 3 POLE MAGNETIC O L RELAY	1	No			0.00	INR Zero Only
17	Supply & Fixing of CT OPERATED THERMAL OVERLOAD RELAY	1	No			0.00	INR Zero Only
18	Supply & Fixing of SINGLE PHASING PREVENTOR WITH MODULE	1	No			0.00	INR Zero Only
19	Supply & Fixing of Isolator Fixed Contact set	1	Set			0.00	INR Zero Only
20	Supply & Fixing of Isolator Moving Contact set	1	Set			0.00	INR Zero Only
21	Supply & Fixing of VACUUM CONTACTOR RECTIFIER BRIDGE	1	No			0.00	INR Zero Only
22	Supply & Fixing of Aux Contactor 110V AC 3 NO plus 1 NC	1	No			0.00	INR Zero Only
23	Supply & Fixing of HT Control Fuse 3 point 3 KV 2 A	1	No			0.00	INR Zero Only
24	Supply & Fixing of DMC moulded 3 point 3 KV insulator for power	1	No			0.00	INR Zero Only
25	Supply & Fixing of Indicating lamp 110V , AC/DC rated for each phase (R/Y/B)	1	No			0.00	INR Zero Only
26	Supply & Fixing of AMP Meter 0-200 A range, 110V, 4" Sq.mm.size	1	No			0.00	INR Zero Only
27	Supply & Fixing of Volt Meter, 0-15KV range, 110V, 4"Sq. mm. size	1	No			0.00	INR Zero Only
28	Supply & Fixing of AUXILIARY CONTACTOR 4 NO plus 4 NC 110V	1	No			0.00	INR Zero Only
29	Wiring with ferruls & Lugs as required	1	Job			0.00	INR Zero Only
	Total impact of GST for the purpose of CTC	1.00	No		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						