

Tender Inviting Authority: Project Engineer (E&M), Purnadih OCP, NK Area, CCL					
Name of the Work / Contract No:	Repair and maintenance of internal wiring, replacement of damaged service connection and allied works of office rooms of Unit Store, Excavation deptt at Quarry-1 Pit Office and under Purnadih OCP NK Area.			NIT No: PE(EnM)/Pnd/NIT/2022-23/22; Dated: 12.08.2022	
	Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)	
ITC Available	Works Contract			Bidder's Status (Mandatory)	Total GST(in Rs.)
Name of the Bidder/ Bidding Firm / Company :				Select	0.00
				GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
				0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Wiring for lighting point/ exhaust fan point /call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface /recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S box and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required. Group A	21	Points		0.00	INR Zero Only
2	Supplying and fixing metal box of 150mm x 75 mm x 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 amps socket outlet and 5/6 amps piano type switch, connection painting etc. as required. (For light plugs to be used in non residential buildings).	6	Nos.		0.00	INR Zero Only
3	Wiring for light/power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit alongwith 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required	50	Metre		0.00	INR Zero Only
4	Supplying and fixing metal box of 180mm x 100 mm x 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 & 15/16 amps socket outlet and 15/16 amps piano type switch, connection painting etc. as required.	4	Nos.		0.00	INR Zero Only
5	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Double pole	2	Nos.		0.00	INR Zero Only
6	Supplying and fixing 3 pin, 5amp ceiling rose on the existing junction box/ wooden block including connection etc as required.	11	Nos.		0.00	INR Zero Only
7	Supplying and fixing brass batten/angle holder including connection etc as required.	7	Nos.		0.00	INR Zero Only

8	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	3	Nos.		0.00	INR Zero Only
9	Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections etc. as required, 32 Amp TP&N	1	Nos.		0.00	INR Zero Only
10	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel PVC conduit as required, 2X6 sq. mm	39	Metre		0.00	INR Zero Only
11	Earthing with G.I. earth pipe 4.5 metre long, 40mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/coke and salt as required.	1	Nos.		0.00	INR Zero Only
12	Providing and fixing 6 SWG dia G.I. on surface or in recess for loop earthing as required	18	Metre		0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1.00	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only