

Tender Inviting Authority: Project Engineer (E&M), Ashok OCP, Piparwar Area							
Name of the Work / Contract No:	Dismantling of 6 span 440v OH lighting line beside dumping and providing and fixing of street light arm for parking area under Ashok OCP.					NIT No. : PO(AK)/PE(E&M)/e-NIT/22-23/77	
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)		To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (Including GST) in Rs. P	BASIC RATE In Figures To be entered by the Bidder (Without GST) in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Dismantling of tubular pole in cement concrete foundation etc. as required	6	No	2221.00		0.00	INR Zero Only
2	Dismantling of over head line comprising of aluminium over head conductor , GI wire , cross arm insulator etc .As required	199.08	Kg	73.00		0.00	INR Zero Only
3	Supplying and fixing of 32 mm dia X 2.00 metres long G.I. pipe (medium class) bracket for mounting of fluorescent / HPMV /HPSV street light fitting on pole including bending the pipe to the required shape, 2 nos 40 mm X 3 mm flat iron clamps with nuts, bolts and washer, painting the flat iron with primer and finish paint etc. as required.	10	No	1012.00		0.00	INR Zero Only
4	Supplying and drawing 2x 1.5 sqmm sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.	30	m	41.00		0.00	INR Zero Only
5	Supplying and drawing 2x4sqmm sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/ PVC conduit as required.	30	m	86.00		0.00	INR Zero Only
6	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						