

Item Rate BoQ

Tender Inviting Authority: Project Engineer(EnM),BIRSA , Barka-Sayal Area, CCL.					
Name of the Work / Contract No:	WIRING OF QTR NO C-2 OF SAUNDA-D OFFICER COLONY	NIT No. : PE(EnM)/BIRSA/e Tender/23-24/07	Dated: 28.04.2023		
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.	28	No.		0.00	INR Zero Only
2	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required 2 X 4 sq. mm + 1 X 4 sq. mm earth wire	45	mtr		0.00	INR Zero Only
3	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	45	mtr		0.00	INR Zero Only
4	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required 3 pin 5/6 A socket outlet	8	no		0.00	INR Zero Only
5	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required. 5/6 amps switch	5	NO		0.00	INR Zero Only
6	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required. 75 mm X 75 mm X 60 mm deep	5	NO		0.00	INR Zero Only
7	PROVIDING 32 Amp switch fuse unit	1	NO		0.00	INR Zero Only
8	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required. 200 mm X 150 mm X 75 mm deep	1	NO		0.00	INR Zero Only
9	Supplying and fixing metal box of 180mm X 100mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 & 15/16 A socket outlet and 15/16 A piano type switch, connections, painting etc. as required	5	NO		0.00	INR Zero Only
10	Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box/ wooden block including connections etc. as required	12	NO		0.00	INR Zero Only
11	Supplying and fixing brass batten/ angle holder including connection etc. as required	8	NO		0.00	INR Zero Only
12	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required	4	NO		0.00	INR Zero Only
13	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required Double pole	2	NO		0.00	INR Zero Only
14	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)	2	No.		0.00	INR Zero Only
15	LED STREET LIGHT	5	NO		0.00	INR Zero Only
16	COPPER WIRE SINGLE CORE 2.5 sq mm	50	mtr		0.00	INR Zero Only
17	ALUMINIUM SERVICE WIRE 2 CORE 6 SQ MM	100	mtr		0.00	INR Zero Only
18	ANGLE WITH CLAMP	5	SET		0.00	INR Zero Only
19	LABOUR COST @ 15% + CONTRACTOR PROFIT @ 10% (SL NO 7,15,16,17 &18)	1	No		0.00	INR Zero Only
20	Total impact of GST for the purpose of CTC	1.000	No.		0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only

Quoted Rate in Words

INR Zero Only