

BIIL OF QUANTITY (BOQ)

Name of Work	<i>Painting and washing of VTC Building and Boundary wall under Amrapali OCP of A-C Area, CCL.</i>		
Manual Quotation No. & Date.	<i>GM (A-C)/SO(C)/Honhey/Hand Quotation/2023-24/09/545, Dt. 18.09.2023</i>		
ITC availabe or Not	<i>ITC available</i>		
Rate of GST (in%)	<i>18%</i>		
Status of Bidder w.r.t. GST {Please mark (v) as applicable	(a)	<i>GST REGISTERED BIDDER UNDER REGULAR SCHEME</i>	
	(b)	<i>GST REGISTERED BIDDER UNDER COMPOSITION SCHEME</i>	
	(c)	<i>GST UNREGISTERED BIDDER</i>	

Sl. No	Description	Quantity	Unit	Rate	Amount	Remarks
1	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats)	1639.22	sqm	41.52	68060.41	
2	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 liters/10 sqm complete induding cost of Priming coat.	1200.96	sqm	67.35	80884.66	
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :One or more coats on old work	267.96	sqm	64.80	17363.81	
				Total=	166308.88	
				GST 18% (+) =	29935.60	
				G.Total Rs.=	196244.48	

I AGREE TO EXECUTE THE WORK at%(in words%) ABOVE/BELOW THE ESTIMATED COST.