

## BILL OF QUANTITY (BOQ) - 01

NAME OF THE WORK	Washing painting including minor repair works at Guard room, store and PS-5 maintenance rooms, boundary walls etc in the premises of Rajrappa Washery under RWP".	
NIQ NO. & DATE	Ref NO. CCL/Rajrappa/GM Unit/Civil/NIQ/2023-24/10 Dated 05.12.2023	
INPUT TAX AVAILABLE / NOT AVAILABLE	AVAILABLE	
RATE OF GST (in%)	18%	
STATUS OF BIDDER W.R.T. GST [PLEASE MARK (v) AS APPLICABLE]	(a)	GST REGISTERED BIDDER UNDER REGULAR SCHEME
	(b)	GST REGISTERED BIDDER UNDER COMPOSITION SCHEME
	(c)	GST UNREGISTERED BIDDER

SL. No.	Description	Qty	Unit	Rate/Unit in Rs.	Amount in Rs	Remark
01	White washing with lime to give an even shade : Old work (two or more coats) .	1500.00	Sqm	13.79	20685.00	14.42.1
02	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 kg/10 sqm) complete.	150.00	Sqm	53.63	8044.50	14.64.2
	Clearing grass and removal of the rubbish up to a distance of 50 m outside the periphery of the area cleared.	95.00	Sqm	501.81	47671.95	2.32
	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed. All kinds of soil	180.00	Cum	209.13	37643.40	2.6.1
	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	200.00	Sqm	72.88	14576.00	14.54.1
	Lettering with black Japan paint of approved brand and manufacture	100.00	units	4.17	417.00	13.71
Total cost of estimate					<b>129037.85</b>	
Add: GST@18%					<b>23226.81</b>	
Grand Total					<b>152264.66</b>	

**Note:** Bidders are requested to quote their rate in figure & words both.

Sd/-

Sd/-

Staff Officer (Civil)

I AGREE TO EXECUTE THE WORK at .....%(in words .....%) ABOVE / BELOW THE ESTIMATED COST.

SIGNATURE OF BIDDER

