

Tender Inviting Authority: Staff Officer Civil Piparwar Area.

Name of Work : Making of footpath from Piparwar workshop to transformer station and wahite washing, painting work at Piparwar workshop under Ashok opencast Project, Piparwar Area.

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	t	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1.01	12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	50.000	sqm	204.15	10207.50	INR Ten Thousand Two Hundred & Seven and Paise Fifty Only
1.02	White washing with lime to give an even shade : old work (two or more coats)	893.840	sqm	13.45	12022.15	INR Twelve Thousand & Twenty Two and Paise Fifteen Only
1.03	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat.	722.980	sqm	82.13	59378.35	INR Fifty Nine Thousand Three Hundred & Seventy Eight and Paise Thirty Five Only
1.04	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	90.140	sqm	63.05	5683.33	INR Five Thousand Six Hundred & Eighty Three and Paise Thirty Three Only
1.05	Dry brick on edge flooring in required pattern with bricks of class designation 7.5 on a bed of 12 mm mud mortar, including filling joints with Jamuna sand, with common burnt clay non modular bricks.	39.520	sqm	514.17	20320.00	INR Twenty Thousand Three Hundred & Nineteen and Paise One Hundred Only
1.06	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	2.960	cum	6182.46	18300.08	INR Eighteen Thousand Three Hundred and Paise Eight Only

1.07	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but excluding cost of reinforcement, with 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.230	cum	7498.61	1724.68	INR One Thousand Seven Hundred & Twenty Four and Paise Sixty Eight Only
1.08	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Thermo-Mechanically Treated bars	18.400	kg	73.63	1354.79	INR One Thousand Three Hundred & Fifty Four and Paise Seventy Nine Only
1.09	Providing and fixing tiled false ceiling of approved materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. GI Metal Ceiling Lay in plain Tegular edge Global white color tiles of size 595x595 mm, and 0.5 mm thick with 8 mm drop; made of G I sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending.	28.800	sqm	1629.35	46925.28	INR Forty Six Thousand Nine Hundred & Twenty Five and Paise Twenty Eight Only
1.10	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					175916.15	INR One Lakh Seventy Five Thousand Nine Hundred & Sixteen and Paise Fifteen Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				