

Validate		Print		Help		Percentage BoQ	
Tender Inviting Authority: Staff Officer(Civil), NK Area.							
Name of Work: Repair and maintenance of septic tank inspection chamber soak pit pipeline at Ashok Vihar Colony under Purnadih Project, NK Area							
Category of Services (To Be Selected by Department)		Category of Bidder( To Be Selected by Bidder)		To Be Entered by Department			
Works Contract		Bidder's Status (Mandatory)		Rate of GST (in %)		GST to be Paid By Bidder (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select		18.00		0.00	
						0.00	
<b>PRICE SCHEDULE</b>							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words	
1	Construction of 10 users Septic tank as per standard design, drawing & instruction of Engineer-in-charge etc all complete.	20.00	Nos	33392.97	667859.40	INR Six Lakh Sixty Seven Thousand Eight Hundred & Fifty Nine and Paise Forty Only	
2	Constructing brick masonry chamber for underground C.I. inspection chamber and bends with 5 class designation bricks in cement mortar 1:5 (1 cement : 5 fine sand ) C.I. cover with frame (light duty) 455 x 610 mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) R.C.C. top slab with 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size ) foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size ), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand ) finished smooth with a floating coat of neat cement on walls and bed concrete etc. complete as per standard design. Inside dimensions 455 x 610 mm and 45 cm deep for single pipe line. With common burnt clay F.P.S. (non modular) bricks of class designation 5	30.00	Nos	4884.8	146544.00	INR One Lakh Forty Six Thousand Five Hundred & Forty Four Only	
3	Constructing soak pit 1.20x1.20x1.20 m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	30.00	Nos	2507.55	75226.50	INR Seventy Five Thousand Two Hundred & Twenty Six and Paise Fifty Only	
4	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work, 50 mm dia nominal bore.	400.00	Metre	610.35	244140.00	INR Two Lakh Forty Four Thousand One Hundred & Forty Only	
5	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work, 80 mm dia nominal bore	200.00	Metre	975.3	195060.00	INR One Lakh Ninety Five Thousand & Sixty Only	
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	25.00	Cum	5420.85	135521.25	INR One Lakh Thirty Five Thousand Five Hundred & Twenty One and Paise Twenty Five Only	
7	Providing, hoisting and fixing up to floor five level precast reinforced concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but excluding cost of reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	8.50	Sqm	7252.9	61649.65	INR Sixty One Thousand Six Hundred & Forty Nine and Paise Sixty Five Only	
8	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars	680.00	Kg	72.05	48994.00	INR Forty Eight Thousand Nine Hundred & Ninety Four Only	
9	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work, 25 mm dia nominal bore	200.00	Metre	336.6	67320.00	INR Sixty Seven Thousand Three Hundred & Twenty Only	
10	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws, including excavation, refilling the earth or cutting of wall and making good the same complete wherever required : 25 mm nominal bore	15.00	Nos	547.95	8219.25	INR Eight Thousand Two Hundred & Nineteen and Paise Twenty Five Only	
11	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws, including excavation, refilling the earth or cutting of wall and making good the same complete wherever required : 50 mm nominal bore	10.00	Nos	959.5	9595.00	INR Nine Thousand Five Hundred & Ninety Five Only	
12	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws, including excavation, refilling the earth or cutting of wall and making good the same complete wherever required : 80 mm nominal bore	10.00	Nos	1215.05	12150.50	INR Twelve Thousand One Hundred & Fifty and Paise Fifty Only	
13	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore	15.00	Nos	532.9	7993.50	INR Seven Thousand Nine Hundred & Ninety Three and Paise Fifty Only	
14	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 50 to 80 mm nominal bore	20.00	Nos	1173.25	23465.00	INR Twenty Three Thousand Four Hundred & Sixty Five Only	
15	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement : 4 fine sand)	300.00	Sqm	252.15	75645.00	INR Seventy Five Thousand Six Hundred & Forty Five Only	
16	Supplying labours, tools and tackles for cleaning filled and choked man hole, septic tank, inspection-chamber, gully pits, sewerage tank etc. in all lift and disposal of spoils upto a lead of 50M all complete as per specification and direction of E.I.	117.11	Cum	673.26	78845.48	INR Seventy Eight Thousand Eight Hundred & Forty Five and Paise Forty Eight Only	
17	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) : 50 mm diameter	15.00	Nos	5318	79770.00	INR Seventy Nine Thousand Seven Hundred & Seventy Only	
18	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) : 80 mm diameter	10.00	Nos	6479.5	64795.00	INR Sixty Four Thousand Seven Hundred & Ninety Five Only	
19	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. All kinds of soil	50.00	Cum	190	9500.00	INR Nine Thousand Five Hundred Only	
20	Carriage of material By Mechanical Transport including loading unloading and stacking Manure or sludge lead upto 1 KM	117.11	Cum	104.67	12257.90	INR Twelve Thousand Two Hundred & Fifty Seven and Paise Ninety Only	
21	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13992 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes, 110 mm diameter	250.00	Metre	251.45	62862.50	INR Sixty Two Thousand Eight Hundred & Sixty Two and Paise Fifty Only	
22	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 25 mm nominal bore	40.00	Nos	431.6	17264.00	INR Seventeen Thousand Two Hundred & Sixty Four Only	
23	Welding by gas or electric plant including transportation of plant at site etc., complete	1500.00	Cm	2.95	4425.00	INR Four Thousand Four Hundred & Twenty Five Only	
24	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only	
<b>Total in Figures</b>					<b>2109102.93</b>	INR Twenty One Lakh Nine Thousand One Hundred & Two and Paise Ninety Three Only	
<b>Quoted Rate in Figures</b>					<b>0.00</b>	INR Zero Only	
<b>Quoted Rate in Words</b>						<b>INR Zero Only</b>	