

| | | | | | |
|---|--|---|-------------------|--|---|
| Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL | | | | | |
| Name of the Work / Contract No: | Work of "Provision of Early Streamer Emission (ESE) Lighting arrester for protection of 4 numbers of rail weighbidges (Two rail weighbidges at Balumath Siding and two rail weighbidges at Phulbasiya Siding) under Magadh OCP, M-S Area." | | | NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/24-25/01; Dated: 05.04.2024. | |
| | Category of Services (To Be Selected by Department) | Category of Bidder (To Be Selected by Bidder) | | | |
| ITC Available | Works Contract | Bidder's Status (Mandatory) | Total GST(in Rs.) | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) |
| Name of the Bidder/ Bidding Firm / Company : | | Select | 0.00 | 0.00 | 0.00 |

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

| NUMBER # | TEXT # | NUMBER | TEXT # | NUMBER # | NUMBER # | TEXT # |
|-----------------------------|---|----------|--------|--|-------------------------------------|-----------------------|
| Sl. No. | Item Description | Quantity | Units | BASIC RATE In Figures To be entered by the Bidder in Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words |
| 1 | 2 | 3 | 4 | 6 | 7 | 8 |
| 1 | <u>Air Terminal</u> Streamer Emission (ESE) type lightning Air terminal. Protection Radius:- 75 Mtr | 4 | No | | 0.00 | INR Zero Only |
| 2 | The mounting pole used to support the lightning air terminal shall be minimum length of 15 mtr each, non corrosive and made up of GI/SS pipe of 80 mm diameter. | 60 | Mtr | | 0.00 | INR Zero Only |
| 3 | <u>Lightning Strike Counter,</u> Non-Electronic & non resettable (Not require any external power supply) type lightning strike counter to count the lightning stroke having display with IP-67 enclosure including all accessories and connection.. (6/7 digit) | 4 | No | | 0.00 | INR Zero Only |
| 4 | <u>Down Conductor,</u> 70 Sq MM insulated Copper Cable for ESE lightning arrester | 60 | Mtr | | 0.00 | INR Zero Only |
| 5 | Providing and installation of Maintenance free Earthing for ESE Lighting Arrester: Using 2 no's of 2 Mtr Long/250 micron, 14.2 mm Dia Copper bonded Steel Rod & Maintenance free Grounding Enhancement backfill Compound For ESE Lightning protection:25 kgs | 8 | Nos | | 0.00 | INR Zero Only |
| 6 | Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required for inter connection of earth pits. | 48 | Mtr | | 0.00 | INR Zero Only |
| 7 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 40mm nominal size) (8X0.91)=0.728 CUM | 0.728 | Cum | | 0.00 | INR Zero Only |
| 8 | Painting with synthetic enamel paint: New work (two or more coats) Synthetic enamel paint in all shades except black or chocolate shade. | 3 | Ltr | | 0.00 | INR Zero Only |
| 9 | Fixing charge of item no 1,2,3,4 for (Roof top/Tower side mounting arrangement & fixing accessories anchoring rope & anchoring plate, Base-for roof top installation) and all miscellaneous accessories like cable connector et required for commissioning @ 15% OF ITEM COST | 1 | Job | | 0.00 | INR Zero Only |
| 10 | Total impact of GST for the purpose of CTC | 1.000 | Job | 0.00 | 0.00 | INR Zero Only |
| Total in Figures | | | | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | | | | | INR Zero Only |