

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL						
Name of the Work / Contract No:	Work of "Diversion/rerouting of LT O/H Line, HT double pole due to infringement of 25 KV High tension line and also dismantling of previously installed tubular pole for freeing the coal loading Zone at Phulbasiya siding Line no:- 01 under Magadh OCP, M-S Area."			NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/24-25/02; Dated: 05.04.2024.		
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Dismantling of over head lines comprising of aluminium over head conductor(10X55X4X0.148)	355	Kg		0.00	INR Zero Only
2	Dismantling of pole/ street light standard/strut embedded in brick ballast foundation etc. as required.	14	Nos		0.00	INR Zero Only
3	Erection of metallic pole of length above 10mtr and upto 12 mtr in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	14	No		0.00	INR Zero Only
4	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required.for 12 number span.	355	Kg		0.00	INR Zero Only
5	Erection of angle Iron/channel iron cross arm on 5 wood/RCC/PCC/steeli tubuiar or Raii poie for 4 wire system.	7	Set		0.00	INR Zero Only
6	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator Inins etc (as per drawing) and painting with primer and finished paint as required.	7	Set		0.00	INR Zero Only
7	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required.	24	Set		0.00	INR Zero Only
8	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required.	8	Set		0.00	INR Zero Only
9	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, bow tightener, 7/3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	5	Set		0.00	INR Zero Only
10	Supply of XLPE insulated and PVC sheathed heavy duty Aerial bunch power cable 1.1 kv grade aluminium unarmoured cable solid/stranded 10 conductor. The cable shall be laid in the air supported by poles as per specification.ABC cable of size 3 CX35+1CX16+1CX25 sq.mm.for Tranformer out put LT side connection.	140	Mtr		0.00	INR Zero Only
11	Fixing Charge of supplied items including end termination of item no 10 at 15%	1	Job		0.00	INR Zero Only
12	Erection of cradle guard as required.	4	No		0.00	INR Zero Only
13	Supply of 6 SWG G.I wire	40	Kg		0.00	INR Zero Only
14	Erection of G.I wire no-6/8 SWG including binding etc.as required for cage cradle and crosslacing.	40	Kg		0.00	INR Zero Only
15	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	