

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghanira Area, CCL			
Name of the Work/ Contract No:	Work of "Provision and connection of service wire with wiring of newly constructed rooms, toilets and kitchen shed at Amarwadih Police Picket & wiring of cabin rooms of Balumath siding used for sample outfitting cum-storage rooms with supply and fixing of industrial type exhaust fan for exhausting the coal dust during sample preparation in Machine room under Magadh O.C.F.M.S Area."	NT No: CM(M-S)/S.O.(E&M)/NT/24-25/3; Dated: 05.04.2024.	
Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)		
ITC Available	Works Contract	Bidder's Status (Mandatory)	
Name of the Bidder/ Bidding Firm/ Company :	Select	Total GST(in Rs.)	
		GST to be Paid By Bidder (in Rs.)	
		GST to be Paid By CIL/Subsidiary (in Rs.)	
		0.00	
		0.00	
		0.00	

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be updated after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. /-	TOTAL AMOUNT Without Taxes in Rs. /-	TOTAL AMOUNT In Words
1	Amarwadih Police Picket	3	4	6	7	8
1	Wiring for light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.	29	Point		0.00	INR Zero Only
2	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/8 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	10	Nos		0.00	INR Zero Only
3	Wiring for circuit/submain wiring alongwith earth wire with the 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.	85	Mtr		0.00	INR Zero Only
4	Wiring for circuit/submain wiring alongwith earth wire with the 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire wire sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.	55	Mtr		0.00	INR Zero Only
5	Wiring for light/power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit	25	Mtr		0.00	INR Zero Only
6	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker single pole and neutral for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required	6	Pcs		0.00	INR Zero Only
7	Providing and fixing following rating and breaking capacity MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making, connections, etc. as required. 100 A, 16 kA, TPMCCB	1	Nos		0.00	INR Zero Only
8	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/recess, complete with lined copper busbar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) way, Double door	1	Nos		0.00	INR Zero Only
9	Provision of Service wire 16 sqmm 2 core Aluminium Armoured cable.	35	Mtr		0.00	INR Zero Only
10	Laying of one number PVC insulated and PVC sheathed/ XLPE power cable of size not exceeding 35 sqmm direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. As required	20	Mtr		0.00	INR Zero Only
11	Earthing with copper earth plate 600 mm X 600 mm X 3mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	1	Nos		0.00	INR Zero Only
12	Providing and fixing 4.00 mm dia copper wire on surface or in recess for vloop earthing as required.	20	Mtr		0.00	INR Zero Only
13	Provision of Wall mounted fan 450 mm, 100 watt, 1400 rpm	4	Nos		0.00	INR Zero Only
14	Provision of Exhaust fan 300 mm sweep	2	Nos		0.00	INR Zero Only
15	Fixing Charge of supplied item no 13 to 14 at 15% of item cost	1	Job		0.00	INR Zero Only
16	Balumath Siding Wiring					
16	Wiring for light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.	47	Point		0.00	INR Zero Only
17	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/8 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	15	Nos		0.00	INR Zero Only
18	Wiring for circuit/submain wiring alongwith earth wire with the 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.	85	Mtr		0.00	INR Zero Only
19	Wiring for light/power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit	40	Mtr		0.00	INR Zero Only
20	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker single pole and neutral for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required	6	Pcs		0.00	INR Zero Only
21	Providing and fixing following rating and breaking capacity MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making, connections, etc. as required. 100 A, 16 KA, TPMCCB	2	Nos		0.00	INR Zero Only
22	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/recess, complete with lined copper busbar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) way, Double door	2	Nos		0.00	INR Zero Only
23	Supply of Service wire 35 sqmm 4 core Aluminium Armoured cable.	35	Mtr		0.00	INR Zero Only
24	Laying of one number PVC insulated and PVC sheathed/ XLPE power cable of size not exceeding 35 sqmm direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. As required	15	Mtr		0.00	INR Zero Only
25	Earthing with copper earth plate 600 mm X 600 mm X 3mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	1	Nos		0.00	INR Zero Only
26	Supply of Wall mounted fan 450 mm, 100 watt, 1400 rpm	7	Nos		0.00	INR Zero Only
27	Supply of Exhaust fan 300 mm sweep	3	Nos		0.00	INR Zero Only
28	Supply of Busbar 100A, 4 Way	1	Nos		0.00	INR Zero Only
29	Supply Onload Manual switch disconnector changer with sheet steel enclosure Type 125 Amp	1	Each		0.00	INR Zero Only
30	Supply of Switch Disconnector with SS Enclosure as required 100 Amp rating	1	Each		0.00	INR Zero Only
31	Fixing Charge of supplied item no 8 & 11 To 15 @15%.	1	Job		0.00	INR Zero Only
32	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	