

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL					
Name of the Work / Contract No:	Work of " Provision of Garden/pathway lighting and area lighting at D-1 Sur Vihar Colony under M-S Area."			NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/24-25/05; Dated: 10.04.2024.	
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Laying of one number PVC insulated and PVC sheathed/ XLPE power cable of 1.1KV grade of size not exceeding 35 sqmm direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. As required	95	Mtr		0.00	INR Zero Only
2	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess,complete with tinned copper bus bar, neutral bus bar, earth bar,din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 2+4 Way/6 way, Double door sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 2+ 4 way/6 way , Double door	35	Nos		0.00	INR Zero Only
3	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required, Double pole	2	Nos		0.00	INR Zero Only
4	Wiring for circuit/ submain wiring alongwith earth wire with thefollowing sizes of FRLS PVC insulated copper conductor, singlecore cable in surface/ recessed medium class PVC conduit as required, 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	68	Mtr		0.00	INR Zero Only
5	Providing and laying in position specific grade of reinforced cement concrete excluding cost of centering,shuttering,finishing and reinforced-All work upto plinth level 1:2:4 (1 cement :2 coarse sand :4 graded stone aggregate 20 mm nominal size) (0.15 cum x 35 no of light Pole)	5.25	Cum		0.00	INR Zero Only
6	50 mm dia. G.I. pipe (Heavy class) for pathway light (1 mtr x 35 pole)	35	Mtr		0.00	INR Zero Only
7	Supply of 4 sqmm 2 core copper armored cable ISI marke	85	Mtr		0.00	INR Zero Only
8	Replacement of post top decorative cast aluminium rust resistance water proof out door pathway/ garden light	35	Each		0.00	INR Zero Only
9	Supply of 2 core flexible copper wire 1.5 sq.mm	40	Mtr		0.00	INR Zero Only
10	Replacement of LED post top Gate Light made in die cast aluminium with innovation glare free indirect lighting distribution & IP 65 protection	2	Nos		0.00	INR Zero Only
11	LED Bulb 9 watt/230v	35	Nos		0.00	INR Zero Only
12	Fixing charge on item no 7 to 11@15%	1	Job		0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	