

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL

Name of the Work / Contract No:	Work of " Earthing of metallic pole of Over head line(415 V, LT Transmission & distribution line) in Public movement areas of Avantika Project office, Weighbridge 07 to new pit office, Chamatu SISF Camp to Checkpost 11 via Weighbridge 13 & 17 under Magadh OCP, MS Area."	NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/24-25/06; Dated: 22.04.2024.
---------------------------------	---	--

Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)
---	---

ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
---------------	----------------	-----------------------------	-------------------	-----------------------------------	---

Name of the Bidder/ Bidding Firm / Company :	Select	0.00	0.00	0.00
--	--------	------	------	------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	50	Nos		0.00	INR Zero Only
2	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required.	150	Mtr		0.00	INR Zero Only
3	Providing and laying in positio cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (1 Cement : 3 coarse sand : 6 raded stone aggregate 40 mm nominal size) (0.45 X 0.45 X 0.45) = 0.091 CUM X 50 = 4.55	4.55	Cum		0.00	INR Zero Only
4	Painting with synthetic enamel paint : New work(two or more coats) Synthetic enamel paint in all shades except blak or chocolate shade.	12.5	Ltr		0.00	INR Zero Only
5	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	