

Tender Inviting Authority: PE(E&M), JRD							
Name of the Work / Contract No:	Bill of quantity for the work "Providing and installation of Aerial Bunches cable for renovation of overhead line with 24 nos Pole painting of Rusted old poles and 2 nos stay set from Jr DAV School Main Road Kathara to VTC Centre JRD under G.M. Unit, Kathara Area .					NIT No. : GM(KTA)/SO(E&M)/GMU/e-Tender/2024-25/09 Date: 03.07.2024.	
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(In Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Providing of PSC pole 200 kg (length 8 mtr.)	4	Nos.			0.00	INR Zero Only
1.02	Erection of RCC/ PCC pole of following length in brick ballast and ramming thefoundation, finishing with 150mm thick cement concrete (1:3:6) layer on top with including excavation and refilling etc as required.Above 6.5 metre and upto 8.0 metre	4	Sets.			0.00	INR Zero Only
1.03	providing of AB bunch cable of size 3X25+1X25 SQ.MM (19 Spanx35m)=665M+ (1 spanx25m)=25m total=690 Mtr.	690	Mtr.			0.00	INR Zero Only
1.04	Supplying and fixing of 32 mm dia X 2.00 metres long G.I. pipe(medium class) bracket for mounting of fluorescent / HPMV / HPSV street light fitting on pole including bending the pipe to the required shape, 2 nos 40 mm X 3 mm flat iron clamps with nuts, bolts and washer, painting the flat iron with primer and finish paint etc. as required.	4	Nos.			0.00	INR Zero Only

1.05	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia x 1.8 mtrs. long stay rod, anchor plate of size 45 cm x 45 cm x 7.5 mm, thimble, stay clamps, turn buckle (20mm x 60cm), 7/3.5mm dia G.I stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement: 3course sand: 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required.	2	Nos.			0.00	INR Zero Only
1.06	Erection of AB bunch cable of size(3X35+1X25) SQ.MM	690	Mtr.			0.00	INR Zero Only
1.07	Supply of all accessories for erecting the AB cable in pole. (Clamp, I Hook, Suspension, connector etc as required)	24	Sets.			0.00	INR Zero Only
1.08	Erection of all accessories for erecting the AB cable in pole. (Clamp, I Hook, Suspension, connector etc as required)	24	Mtr.			0.00	INR Zero Only
1.09	Supplying of 2C x 2.5 sq. mm Copper cable PVC Insulated	42	Mtr.			0.00	INR Zero Only
1.10	Providing of PVC Junction Box with connector	2	Nos.			0.00	INR Zero Only
1.11	Providing and installation of timer switch complete set of rating 150 amp	1	Nos.			0.00	INR Zero Only
1.12	Old Pole painting (with one coat red-oxide paint and aluminium paint with bracket) No. of one (01) no. 12Mtrs Tubular Pole	20	Nos.			0.00	INR Zero Only
1.13	Labour charge of above item no 1.09 & 1.10	1	LS			0.00	INR Zero Only
2	<b>Total impact of GST for the purpose of CTC</b>	1	No.		0.00	0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>					