

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Project Engineer (E&M), Dhori (K) Colliery

Name of the Work / Contract No:	Providing and fixing of garden light near Manager office, E&M office, near canteen at 7, 8 incline office and arrangement of safety and fencing near some office in r/o Dhori (K) colliery.	NIT/D(K)/24-25/E&M/04/01			
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected)			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Part-A					
1.01	Supply of garden light.	30	No		0.00	INR Zero Only
1.02	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 50 mm dia. nominal bore	30	M		0.00	INR Zero Only
1.03	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size in phenolic laminated sheet cover in front including painting etc required. : 200 mm x 125 mm x 60 mm deep.	30	No		0.00	INR Zero Only
1.04	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	50	M3		0.00	INR Zero Only
1.05	Supplying and fixing of following sizes of medium class PVC conduit, along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required. : 25 mm	150	M		0.00	INR Zero Only
1.06	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. 2 x 6 sq.mm + 1 x 6 sq.mm earth wire.	200	M		0.00	INR Zero Only
1.07	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. 2x1.5 sq.mm + 1x1.5 sq.mm earth wire.	100	M		0.00	INR Zero Only
1.08	Supply & fixing of fuse 5 Amp.	30	No		0.00	INR Zero Only
1.09	Supply of 12W LED bulb.	30	No		0.00	INR Zero Only
1.1	Labour cost for fixing of garden light	30	No		0.00	INR Zero Only
2	Part-B					

2.01	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	2.5	M3		0.00	INR Zero Only
2.02	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work upto plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size).	2.5	ME		0.00	INR Zero Only
2.03	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	964.72	KG		0.00	INR Zero Only
2.04	Steel jali.	63.1	M2		0.00	INR Zero Only
2.05	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.	138.2	M2		0.00	INR Zero Only
5	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					