

Tender Inviting Authority: Staff officer(E&M), Dhori Area.							
Name of the Work / Contract No:	Re-organisation of LT OH line at Chapri Rest House under CCD, GM Unit, Dhori Area						
	Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Select	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CI/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :				18	0.00	0.00	0.00
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Supply of cement pole 8 m long	2	Nos.			0.00	INR Zero Only
1.02	Erection of RCC/PCC pole of following length in brick ballast and ramming the foundation, finishing with 150 mm thick cement concrete (1:3:6) layer on top with including excavation and re-filling etc. as required. : Above 6.5 metre and upto 8 metre	2	Nos.			0.00	INR Zero Only
1.03	Dismantling of pole/street light standard/strut embedded in cement concrete foundation etc. as required	4	Nos.			0.00	INR Zero Only
1.04	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including conduit as required. 40 mm	9	set			0.00	INR Zero Only
1.05	Supplying of channel iron 75 mm x 40 mm x 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required	18	set			0.00	INR Zero Only
1.06	Erection of angle iron/ channel iron cross arm on RCC/PCC/ steel tubular/ rail pole etc. as required	27	set			0.00	INR Zero Only
1.07	Dismantling of overhead lines comprising of copper/aluminium overhead conductor, G.I. wire cross arms, insulators etc. as required 5 span x 5 wire x 40 mtr. x 0.214kg	214	kg			0.00	INR Zero Only
1.08	Supply of 5 core, 65 sqmm cable	160	m			0.00	INR Zero Only
1.09	Erection of ACSR conductor of 7/2.11mm to 7/3.00mm diameter including binding etc as required. 5 wire x 2 x 40 x 0.214 = 85.6 kg	85.6	kg			0.00	INR Zero Only
1.11	Erection of 5 core x 65 sqmm cable cable	135	m			0.00	INR Zero Only
1.11	Welding	120	inch			0.00	INR Zero Only
1.12	Dismantling of old light fitting	10	Nos.			0.00	INR Zero Only
1.13	Erection of light fitting	8	Nos.			0.00	INR Zero Only
1.14	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia x 1.8 metres long stay rod, anchor plate of size 45 cm x 45 cm x 7.5 mm, thimble, stay clamps, turn buckle (20 mm x 60 cm), 7/3.15 mm dia G.I. stay wire and strain wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required	2	set			0.00	INR Zero Only
1.15	Erection of steel pole tubular or rail pole strut concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and re-filling and secured with holding clamps, bolts, nuts, etc. as required	1	No.			0.00	INR Zero Only
1.16	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc with charcoal/coke and salt as required	4	Nos.			0.00	INR Zero Only
1.17	Providing and fixing 25 mm X 5 mm GI strip on surface or in recess for connections etc as required	40	m			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1.000	Nos			0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						

Tender Inviting Authority: Staff officer(E&M), Dhori Area.

Name of the Work / Contract No:	Maintenance of 440 V, 3phase, 4 wire system OH line spacer and changing of pin, shackle, insulator in Modi dhoura under SDOCM, Dhori Area					
	Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Erection of AAR conductor of 7/2.11 mm to 7/3.00 mm diameter including binding etc. as required. Dismantle & erection of old line.	547.84	kg			0.00	INR Zero Only
1.02	Bush cutting for execution of work	600	sqm			0.00	INR Zero Only
1.03	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle (20 mm X 60cm), 7/ 3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	5	sets			0.00	INR Zero Only
1.04	Fitting and fixing of OH line spacer	64	nos			0.00	INR Zero Only
1.05	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required .	20	nos			0.00	INR Zero Only
1.06	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required .	15	nos			0.00	INR Zero Only
1.07	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	10	nos			0.00	INR Zero Only
1.08	Erection of angle iron/ channel iron cross arm on wood/ RCC/ PCC/ steel tubular/ rail pole etc. as required.	12	nos			0.00	INR Zero Only
1.09	Providing of 8 SWG G.I. wire for cradling	132.96	kg			0.00	INR Zero Only
1.1	Erection of cradle guard	250	nos			0.00	INR Zero Only
1.11	Applying priming coat : With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works.	150	sqm			0.00	INR Zero Only
1.12	Painting with aluminium paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	150	sqm			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						

Tender Inviting Authority Staff office@BAM, Dhori Area.							
Name of the Work /Contract No.	Repairing and overhauling of 04 nos. VCB starters attached with different capacity motor pump set installed at SDOCA, Dhori Area						
Category of Services (To Be Selected by Department)	Category of Services (To Be Selected by Bidder)						
ITC Available	Works Contract						
Name of the Bidder/Bidding Firm / Company	Bidder's Name (Bidder's Code)						
	Rate of ITC (Rs./sq)		GST to be Paid by Bidder (In Rs.)		GST to be Paid by CU/Subsidiary (In Rs.)		
	18		0.00		0.00		
BID SCHEDULE							
(This BQ template must not be modified/replaced by the bidder and the same should be updated after filling the relevant columns, else the Bidder's Table to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
Sl. No.	Item Description	Quantity	UNIT	ESTIMATED Rate in Rs. /-	MARK RATE TO BE EXPANDED BY BIDDER IN RS. /-	TOTAL AMOUNT/Without Taxes in Rs. /-	TOTAL Amount in Words
1	2	3	4	5	6	7	8
1.01	Part A: 3.3 KV, VCB DOL type, Make: Protindia, SI no. KPST-1	1	nos			0.00	Nil Zero Only
1.02	Providing of Ferrule, lugs, clips, socket wiring boxes for circuit wiring.	1	job			0.00	Nil Zero Only
1.03	Providing of Tracthawk switch MOC/AJUBA type.	1	nos			0.00	Nil Zero Only
1.04	Providing of make contact in isolator.	3	nos			0.00	Nil Zero Only
1.05	Providing of Ferrule contact in isolator.	3	nos			0.00	Nil Zero Only
1.06	Providing of Air-mat: 4" x 4" size digital type, 5amp operated, different 100V, etc.	1	nos			0.00	Nil Zero Only
1.07	Providing of 1/2" x 3/8x1/2" single phase dry type OLV.	1	nos			0.00	Nil Zero Only
1.08	After repairing of circuit of protective relays testing by secondary injectors/relay testing machine as well as testing/ measuring of meters, indicators etc.	1	job			0.00	Nil Zero Only
1.09	Complete body cleaning, double coat primer and enamel painting by spray painting machine including cost of cleaning and painting materials as well as labor cost.	1	job			0.00	Nil Zero Only
1.1	Repairing/ lubing, overhauling of operating mechanism cleaning, washing by suitable oil. Providing of lubricants in all moving joints, etc.	1	job			0.00	Nil Zero Only
1.11	Repairing & modification of control circuit wiring.	1	job			0.00	Nil Zero Only
1.12	Overhauling of bus bar system with repairing by drilling, cutting, shape making and setting, as well as complete insulation covering.	1	job			0.00	Nil Zero Only
1.13	Repairing/ overhauling and commissioning of starters, such as insulation painting of all insulators, P.T, C.T etc as well as Tightening of all loose connections/joints.	1	job			0.00	Nil Zero Only
1.14	Supervision, incident& overhead expenses.	1	job			0.00	Nil Zero Only
1.15	Part B: 3.3 KV, VCB DOL type, Make: S&M Mine Line, SI no.: 1456	1	nos			0.00	Nil Zero Only
1.16	Providing of Air-mat: 4" x 4" size digital type, 5amp operated, different 100V, etc.	1	nos			0.00	Nil Zero Only
1.17	Providing of Single phase protection 120V.	1	nos			0.00	Nil Zero Only
1.18	Providing of Ferrule, lugs, clips, socket wiring boxes for circuit wiring.	1	job			0.00	Nil Zero Only
1.19	Providing of OLV-relay C type(air-insulated) based.	1	nos			0.00	Nil Zero Only
1.2	Providing of Air-mat: 4" x 4" size digital type, 5amp operated, different 100V, etc.	1	nos			0.00	Nil Zero Only
1.21	Providing of Ferrule contact in isolator.	3	nos			0.00	Nil Zero Only
1.22	Providing 1/2 nos type from (Balthas type)4amp.	2	nos			0.00	Nil Zero Only
1.23	Providing of 2.5 gpm single core flexible copper wire standard quality, 1.1KV grade.	1	nos			0.00	Nil Zero Only
1.24	Providing of Volt meter 4" x 4" size, digital type, P.T.R 3.3KV/120V.	1	nos			0.00	Nil Zero Only
1.25	After repairing of circuit of protective relays testing by secondary injectors/relay testing machine as well as testing/ measuring of meters, indicators etc.	1	job			0.00	Nil Zero Only
1.26	Complete body cleaning, double coat primer and Enamel painting by Spray painting machine including cost of cleaning and painting materials as well as labor cost.	1	job			0.00	Nil Zero Only
1.27	Repairing/ lubing, overhauling of operating mechanism cleaning, washing by suitable oil. Providing of lubricants in all moving joints, etc.	1	job			0.00	Nil Zero Only
1.28	Repairing & modification of control circuit wiring.	1	job			0.00	Nil Zero Only
1.29	Overhauling of bus bar system with repairing by drilling, cutting, shape making and setting, as well as complete insulation covering.	1	job			0.00	Nil Zero Only
1.3	Repairing/ overhauling and commissioning of starters, such as insulation painting of all insulators, P.T, C.T etc as well as Tightening of all loose connections/joints.	1	job			0.00	Nil Zero Only
1.31	Supervision, incident& overhead expenses.	1	job			0.00	Nil Zero Only
1.32	Part C: 3.3 KV, VCB DOL type, Make: S&M Mine Line, SI no.: 1340	1	nos			0.00	Nil Zero Only
1.33	Providing 1/2 nos type from (Balthas type)4amp.	2	nos			0.00	Nil Zero Only
1.34	Providing of Air-mat: 4" x 4" size digital type, 5amp operated, different 100V, etc.	1	nos			0.00	Nil Zero Only
1.35	Providing of Tracthawk switch MOC/AJUBA type.	1	nos			0.00	Nil Zero Only
1.36	Providing of Ferrule, lugs, clips, socket wiring boxes for circuit wiring.	1	job			0.00	Nil Zero Only
1.37	Providing of Ferrule contact in isolator.	3	nos			0.00	Nil Zero Only
1.38	Providing of Ferrule contact in isolator.	3	nos			0.00	Nil Zero Only
1.39	Providing of Single phase protection 120V.	1	nos			0.00	Nil Zero Only
1.4	After repairing of circuit of protective relays testing by secondary injectors/relay testing machine as well as testing/ measuring of meters, indicators etc.	1	job			0.00	Nil Zero Only
1.41	Complete body cleaning, double coat primer and Enamel painting by Spray painting machine including cost of cleaning and painting materials as well as labor cost.	1	job			0.00	Nil Zero Only
1.42	Repairing/ lubing, overhauling of operating mechanism cleaning, washing by suitable oil. Providing of lubricants in all moving joints, etc.	1	job			0.00	Nil Zero Only
1.43	Repairing & modification of control circuit wiring.	1	job			0.00	Nil Zero Only
1.44	Overhauling of bus bar system with repairing by drilling, cutting, shape making and setting, as well as complete insulation covering.	1	job			0.00	Nil Zero Only
1.45	Repairing/ overhauling and commissioning of starters, such as insulation painting of all insulators, P.T, C.T etc as well as Tightening of all loose connections/joints.	1	job			0.00	Nil Zero Only
1.46	Supervision, incident& overhead expenses.	1	job			0.00	Nil Zero Only
1.47	Part D: 3.3 KV, VCB DOL type, Make: Protindia, SI no.: HQ42	1	nos			0.00	Nil Zero Only
1.48	Providing of Ferrule, lugs, clips, socket wiring boxes for circuit wiring.	1	job			0.00	Nil Zero Only
1.49	Providing of 2.5 gpm single core flexible copper wire standard quality, 1.1KV grade.	1	nos			0.00	Nil Zero Only
1.5	Providing of OLV-relay C type(air-insulated) based.	1	nos			0.00	Nil Zero Only
1.51	Providing of Ferrule contact in isolator.	3	nos			0.00	Nil Zero Only
1.52	Providing of Single phase protection 120V.	1	nos			0.00	Nil Zero Only
1.53	Providing 1/2 nos type from (Balthas type)4amp.	6	nos			0.00	Nil Zero Only
1.54	After repairing of circuit of protective relays testing by secondary injectors/relay testing machine as well as testing/ measuring of meters, indicators etc.	1	job			0.00	Nil Zero Only
1.55	Complete body cleaning, double coat primer and Enamel painting by Spray painting machine including cost of cleaning and painting materials as well as labor cost.	1	job			0.00	Nil Zero Only
1.56	Repairing/ lubing, overhauling of operating mechanism cleaning, washing by suitable oil. Providing of lubricants in all moving joints, etc.	1	job			0.00	Nil Zero Only
1.57	Repairing & modification of control circuit wiring.	1	job			0.00	Nil Zero Only
1.58	Overhauling of bus bar system with repairing by drilling, cutting, shape making and setting, as well as complete insulation covering.	1	job			0.00	Nil Zero Only
1.59	Repairing/ overhauling and commissioning of starters, such as insulation painting of all insulators, P.T, C.T etc as well as Tightening of all loose connections/joints.	1	job			0.00	Nil Zero Only
1.6	Supervision, incident& overhead expenses.	1	job			0.00	Nil Zero Only
2	Total Impact of GST for the purpose of ITC	1.000	Nos			0.00	Nil Zero Only
Total in Figures						0.00	Nil Zero Only
Quoted Rate in Words						INR Zero Only	

Tender Inviting Authority: Staff Officer(EAM), Dhori Area.								
Name of the Work / Contract No.	Mechanical repairing of HT motors (A) 160KW, 3.3KV 148SRPM, Make: Marathon, SI no.: F30526/1 (B) 335HP, 1480RPM, Make: Crompton Greaves, SI no.: 355198072-1 (C) 215KW, 3.3 KV grade, Make: Marathon, SI no.: KMP-1 installed at SDOCM, Dhori Area							
Category of Services (To Be Selected by Department)	Works Contract							
ITC Available	Works Contract							
Name of the Bidder / Bidding Firm / Company:	Select							
	Bidder's Status (Manufacturer)		Rate of GST (in %)		Total GST(In Rs.)		GST to be Paid By Bidder (in Rs.)	
	18		0.00		0.00		0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. #	BASIC RATE in Figures To Be entered by the Bidder in Rs. #	TOTAL AMOUNT Without Tax in Rs. #	TOTAL AMOUNT in Words	
1	2	3	4	5	6	7	8	
1.01	Part A: 160KW, 3.3KV 148SRPM, Make: Marathon, SI no.: F30526/1	1	job			0.00	INR Zero Only	
1.02	M.S sheet cooling fan cover new making & fabrication as per sample and size by M.S Sheet cutting, required bending, framing all joints full welding, side covering cooling net making, fixing welding, hole center making for tightening.	1	no.			0.00	INR Zero Only	
1.03	Rotor shaft bearing housing repairing by electrode welding on bearing fitting place or sleeve making as per bearing size.	2	job.			0.00	INR Zero Only	
1.04	Repairing and setting of terminal box and new making of its cover by iron sheet.	1	job.			0.00	INR Zero Only	
1.05	Complete motor set dismantling, After repairing work its complete assembling/commissioning with testing checking charge.	1	job.			0.00	INR Zero Only	
1.06	cooling fan new making as per sample with casting, machining, drilling tapping, new hub making & tightening with key ways cutting, alignment & balancing on lathe machine with material.	1	no.			0.00	INR Zero Only	
1.07	Complete motor coil cleaning after cleaning its varnishing/heating, tapping etc.	1	job.			0.00	INR Zero Only	
1.08	End cover housing repairing by CI electrode welding and machining and per bearing size.	2	no.			0.00	INR Zero Only	
1.09	Gas heating and cutting grinding etc. Work of both end connection points, strip bars for old damage bar dismantling from rotor.	60	no.			0.00	INR Zero Only	
1.1	After repairing and changing of strips bars complete new brazing of both end points by gas heating, silver rod brazing and copper bars shape making of rotor strips bar after this bars fixing in same slots.	60	no.			0.00	INR Zero Only	
1.11	Rotor and rotor shaft alignment checking on lathe machine and rectification & its alignment setting by cut machining and polishing by stone file & complete balance checking.	1	job.			0.00	INR Zero Only	
1.12	Old and damage both side bearing housing opening by puller and gas heating /cutting after opening of bearing new bearing fitting /setting.	2	no.			0.00	INR Zero Only	
1.13	Supervision , incidental & overhead expenses	1	job.			0.00	INR Zero Only	
1.15	Part B: 335HP, 1480RPM, Make: Crompton Greaves, SI no.: 355198072-1	1	job.			0.00	INR Zero Only	
1.16	Rotor and rotor shaft alignment checking on lathe machine and rectification & its alignment setting by cut machining and polishing by stone file & complete balance checking.	1	job.			0.00	INR Zero Only	
1.17	Old and damage both side bearing housing opening by puller and gas heating /cutting after opening of bearing new bearing fitting /setting.	2	no.			0.00	INR Zero Only	
1.18	Complete motor coil cleaning after cleaning its varnishing/heating, tapping etc.	1	job.			0.00	INR Zero Only	
1.19	End cover housing repairing by CI electrode welding and machining and per bearing size.	2	no.			0.00	INR Zero Only	
1.2	cost of coil molding charge.	60	coil			0.00	INR Zero Only	
1.21	cooling fan new making as per sample with casting, machining, drilling tapping, new hub making & tightening with key ways cutting, alignment & balancing on lathe machine with material.	1	no.			0.00	INR Zero Only	
1.22	Complete motor coil cleaning after cleaning its varnishing/heating, tapping etc.	1	job.			0.00	INR Zero Only	
1.23	M.S sheet cooling fan cover new making & fabrication as per sample and size by M.S Sheet cutting, required bending, framing all joints full welding, side covering cooling net making, fixing welding, hole center making for tightening.	1	no.			0.00	INR Zero Only	
1.24	Rotor shaft bearing housing repairing by electrode welding on bearing fitting place or sleeve making as per bearing size.	2	job.			0.00	INR Zero Only	
1.25	Repairing and setting of terminal box and new making of its cover by iron sheet.	1	job.			0.00	INR Zero Only	
1.26	Supervision , incidental & overhead expenses	1	job.			0.00	INR Zero Only	
1.32	Part C: 215KW, 3.3 KV grade, Make: Marathon, SI no.: KMP-1	1	job.			0.00	INR Zero Only	
1.33	End cover housing repairing by CI electrode welding and machining and per bearing size.	2	no.			0.00	INR Zero Only	
1.34	M.S sheet cooling fan cover new making & fabrication as per sample and size by M.S Sheet cutting, required bending, framing all joints full welding, side covering cooling net making, fixing welding, hole center making for tightening.	1	no.			0.00	INR Zero Only	
1.35	Rotor and rotor shaft alignment checking on lathe machine and rectification & its alignment setting by cut machining and polishing by stone file & complete balance checking.	1	job.			0.00	INR Zero Only	
1.36	Repairing and setting of terminal box and new making of its cover by iron sheet.	1	job.			0.00	INR Zero Only	
1.37	Rotor shaft bearing housing repairing by electrode welding on bearing fitting place or sleeve making as per bearing size.	2	job.			0.00	INR Zero Only	
1.38	cooling fan new making as per sample with casting, machining, drilling tapping, new hub making & tightening with key ways cutting, alignment & balancing on lathe machine with material.	1	no.			0.00	INR Zero Only	
1.39	Gas heating and cutting grinding etc. Work of both end connection points, strip bars for old damage bar dismantling from rotor.	60	no.			0.00	INR Zero Only	
1.4	After repairing and changing of strips bars complete new brazing of both end points by gas heating, silver rod brazing and copper bars shape making of rotor strips bar after this bars fixing in same slots.	60	no.			0.00	INR Zero Only	
1.41	Complete motor coil cleaning after cleaning its varnishing/heating, tapping etc.	1	job.			0.00	INR Zero Only	
1.42	Supervision , incidental & overhead expenses	1	job.			0.00	INR Zero Only	
2	Total Impact of GST for the purpose of CTC	1.000	Nos			0.00	INR Zero Only	
Total in Figures:						0.00	INR Zero Only	
Quoted Rate in Words	INR Zero Only							

Tender Inviting Authority: Staff officer(E&M), Dhori Area.							
Name of the Work / Contract No:	Fabrication, installation and commissioning of 01 no LT Control Panel at CHD under GM unit Dhori Area.						
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By ClL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.00
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7	8
1.01	Wiring with ferrul and lugs as required	1	No			0.00	INR Zero Only
1.02	Supply & Fixing of Aluminium flat	28	Kg			0.00	INR Zero Only
1.03	Supply & Fixing of 250A 36KA MCCB with spreader & EROH thermal based with O/L/S/T shunt relay set	2	No			0.00	INR Zero Only
1.04	Supply and fixing of 250/5 CL1.0 15VA CT	6	No			0.00	INR Zero Only
1.05	Supply and fixing of neutral link	2	No			0.00	INR Zero Only
1.06	Supply and fixing of 250A FP change over with ROM set	2	No			0.00	INR Zero Only
1.07	Supply and fixing of 63A DP MCB 10KA	2	No			0.00	INR Zero Only
1.08	Supply and fixing of 32A DP MCB 10KA	6	No			0.00	INR Zero Only
1.09	Supply and fixing of POWER TB	20	No			0.00	INR Zero Only
1.1	Fabrication, installation and commissioning of MS enclosure Powder Coated MS Enclosure made out of 2/1.6mm CRCA Sheet with Base channel of 50mm in black shade with gaskets, Lifting Hooks, Locks & Hinged Door Cable Entry :- BOTTOM	1	No			0.00	INR Zero Only
1.11	Supply and fixing of 250A TPN TP E-91 Grade Aluminium Busbar and Horizontal and Vertical Busbar as per load with Color Coded Heat Shrinkable PVC Sleeves R,Y,B Phase : 1 x 25mm x 10mm, NEUTRAL Bus : 1 x 25mm x 06mm	1	No			0.00	INR Zero Only
1.12	Supply & Fixing of control MCB 6A SP10KA curve	6	No			0.00	INR Zero Only
1.13	Supply & Fixing of Glass tape	15	Roll			0.00	INR Zero Only
1.14	Supply & Fixing of Amp Meter/Volt Meter	12	No			0.00	INR Zero Only
1.15	Supply & Fixing of Indicating lamp	12	No			0.00	INR Zero Only
1.16	Supply and fixing of copper lugs 195 Ampere	12	No			0.00	INR Zero Only
1.17	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. Above 35 sq. mm and upto 95 sq. mm	347	mtr			0.00	INR Zero Only
1.18	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required: 40mm	89	mtr			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						