

Estimate for : Urgent Repair/maintenance of track line of Dhori siding of AADOCM of Dhori Area

Sl. No.	Description of Item	Unit	Quantity	Updated Rate	Amount	Remarks
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m,	Cum	272.00	128.05	34829.60	CCL SOR 2.6.1
2	Maintenance of railway siding such as repair of rail, tightning of nut & volt , fish plate, liners, pandle clip etc. As per direction of E/C.	Day	15.00	4946.47	74197.05	A/R
3	Providing/fixing of spendel clip as per specification railway standard T-3701.	Each	20.00	172.50	3450.00	A/R
4	Providing/fixing of Fish Plate 60KG of as per specification of railway standard - T-1898	Each	4.00	8970.00	35880.00	A/R
5	Providing/fixing of nut volt as per specification of railway of standard size 25X140	Each	16.00	195.50	3128.00	A/R
6	Providing/fixing of Rubber as per specification of railway of Standard T-3711	Each	16.00	69.00	1104.00	A/R
7	Providing/fixing of GFN Liner as per specification of railway of standard size T-3706	Each	20.00	80.50	1610.00	A/R
8	Providing/fixing of Metal Liner as per specification of railway of standard size RT-3740	Each	20.00	184.00	3680.00	A/R
	TOTAL				157878.65	
	GST @ 18 %				28418.157	
	G. TOTAL				186296.81	

Engg. Asst.(Civil)

**Project
Engg.(Civil)**