

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:	Complete repairing of VCB Switch (a) 6.6kV/3.3kV, 1250 Amp Make Andrew Yule, Sl. No. 3124 supplying power to Shovel Feeder installed at Dakra Substation and (b) 6.6kV/3.3kV/110V, CT 120-60/5.5 Amp. Make Electrokechnika at Dakra Substation under Dakra Project, NK Area	NIT No. GM (NK)/EnM/eNIT/2024-25/119; dated 23.07.2024.			
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Complete repairing of VCB Switch (a) 6.6kV/3.3kV, 1250 Amp Make Andrew Yule, Sl. No. 3124 supplying power to Shovel Feeder installed at Dakra Substation					
2	HT Circuit Spout 6.6kV insulator	5.00	Nos		0.00	INR Zero Only
3	Auxiliary contactor 110V AC	1.00	Nos		0.00	INR Zero Only
4	Indicator 110V AC/DC	4.00	Nos		0.00	INR Zero Only
5	Push buttons switch	2.00	Nos		0.00	INR Zero Only
6	Copper strip 50x6 mm	12.00	Mtr		0.00	INR Zero Only
7	CBCT 3.3kV	1.00	Nos		0.00	INR Zero Only
8	Earth Leakage Relay 110V, 5 Amp	1.00	Nos		0.00	INR Zero Only
9	Rectifier Capacitor Bank, 110V AC/DC	1.00	Nos		0.00	INR Zero Only
10	Sun Trip Coil 110V DC	1.00	Nos		0.00	INR Zero Only
11	Wiring with material (1.5 sqmm Copper wire, lugs etc)	1.00	Nos		0.00	INR Zero Only
12	Mechanism Repairing	1.00	Set		0.00	INR Zero Only
13	Labour charge of Item No. 2 to 10	1.00	job		0.00	INR Zero Only
14	Complete repairing of VCB Switch 6.6kV/3.3kV/110V, CT 120-60/5.5 Amp. Make Electrokechnika at Dakra Substation					
15	HT Circuit Spout 6.6kV 04 hole insulator	8.00	Nos		0.00	INR Zero Only
16	Auxiliary contactor 110V AC	1.00	Nos		0.00	INR Zero Only
17	Indicator 110V AC/DC	4.00	Nos		0.00	INR Zero Only
18	Push buttons switch	2.00	Nos		0.00	INR Zero Only
19	P.T 3.3kV/110V AC	1.00	Set		0.00	INR Zero Only
20	Copper strip 50x6 mm	12.00	Mtr		0.00	INR Zero Only
21	CBCT 3.3kV	1.00	Nos		0.00	INR Zero Only
22	Earth Leakage Relay 110V, 5 Amp	1.00	Nos		0.00	INR Zero Only
23	Rectifier Capacitor Bank, 110V AC/DC	1.00	Nos		0.00	INR Zero Only
24	Bus Bar insulation (50x6) mm	18.00	Mtr		0.00	INR Zero Only
25	Voltmeter 96 sqmm PTR 3.3kV/110V AC	1.00	Nos		0.00	INR Zero Only
26	Ammeter 96 sqmm 120-60/5.5 Amp	1.00	Nos		0.00	INR Zero Only
27	Mechanism Repairing	1.00	Set		0.00	INR Zero Only
28	Labour charge of Item No. 15 to 26	1.00	job		0.00	INR Zero Only
29	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>	<b>INR Zero Only</b>					