

Item Rate BoQ

| Tender Inviting Authority: Staff Officer(Excavation) Kuju Area | | | | | | | |
|---|--|---|--------------------|-----------------------------|--|---|-----------------------|
| Name of the Work / Contract No: Repairing/maintaining of air conditioning system and fitment of cabin fan in different HEMMs (05 nos.) (Dozers sl. no. 13738, 13718, 13644 and Drills sl. no. 6846,906) deployed at Topa OCP, Kuju Area. | | | | | | NIT No. : GM(K)/Excv-61/24-25/T-20 | |
| Category of Services (To Be Selected by Department) | | Category of Bidder (To Be Selected by Bidder) | | To Be Entered by Department | | | |
| ITC Available | Works Contract | Bidder's Status (Mandatory) | Rate of GST (in %) | Total GST(in Rs.) | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) | |
| Name of the Bidder/ Bidding Firm / Company : | | Select | 18 | 0.00 | 0.00 | 0.00 | |
| PRICE SCHEDULE | | | | | | | |
| (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) | | | | | | | |
| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER # | NUMBER # | NUMBER # | TEXT # |
| Sl. No. | Item Description | Quantity | Units | Estimated Rate in Rs. P | BASIC RATE In Figures To be entered by the Bidder in Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| 1 | Material Cost for repairing of A/C system | | | | | | |
| 1.01 | Replacement of Blower motor | 3.0 | No. | | | 0.00 | INR Zero Only |
| 1.02 | Replacement of condenser coil | 4.0 | No. | | | 0.00 | INR Zero Only |
| 1.03 | Repairing of compressure assy. clutch side | 3.0 | No. | | | 0.00 | INR Zero Only |
| 1.04 | Compressor oil 250ML | 5.0 | No. | | | 0.00 | INR Zero Only |
| 1.05 | Dryer filter | 5.0 | No. | | | 0.00 | INR Zero Only |
| 1.06 | A/C pipe compressor to conductor size 3/4" | 4.0 | No. | | | 0.00 | INR Zero Only |
| 1.07 | A/C pipe compressor to cooling coil size 1" | 80.0 | Fl. | | | 0.00 | INR Zero Only |
| 1.08 | Connector No. 8 male 90 | 4.0 | No. | | | 0.00 | INR Zero Only |
| 1.09 | Connector No. 8 Straight | 4.0 | No. | | | 0.00 | INR Zero Only |
| 1.1 | A/C "O" Ring | 5.0 | No. | | | 0.00 | INR Zero Only |
| 1.11 | Binary A/C safety switch | 5.0 | No. | | | 0.00 | INR Zero Only |
| 1.12 | Filling of R 134 Gas | 20.0 | No. | | | 0.00 | INR Zero Only |
| 1.13 | Repairing and fabrication of blower motor box assy. and foundation | 4.0 | No. | | | 0.00 | INR Zero Only |
| 1.14 | Compressor bracket adjuster, Rod | 5.0 | No. | | | 0.00 | INR Zero Only |
| 1.15 | Flashing leakage testing | 5.0 | No. | | | 0.00 | INR Zero Only |
| 1.16 | Replacement expansion valve | 5.0 | No. | | | 0.00 | INR Zero Only |
| 1.17 | Fabrication of condenser box & foundation | 4.0 | No. | | | 0.00 | INR Zero Only |
| 1.18 | LT Wire 5mm | 5.0 | No. | | | 0.00 | INR Zero Only |
| 1.19 | LT Wire 6mm | 5.0 | No. | | | 0.00 | INR Zero Only |
| 1.20 | Conduit PVC Cover | 5.0 | No. | | | 0.00 | INR Zero Only |
| 1.21 | Cabin Fan 24 Volt | 5.0 | No. | | | 0.00 | INR Zero Only |
| 1.22 | Cost of adhesive/PVC tape & fastener | 5.0 | No. | | | 0.00 | INR Zero Only |
| 2 | Labour Cost | | | | | | |
| 2.1 | Skilled manpower | 20.0 | SFT | | | 0.00 | INR Zero Only |
| 2.2 | Helper | 20.0 | SFT | | | 0.00 | INR Zero Only |
| 2.3 | Supervisor | 10.0 | SFT | | | 0.00 | INR Zero Only |
| 3 | 10% Contractor's Profit | 1.0 | No. | | | 0.00 | INR Zero Only |
| 4 | Total impact of GST for the purpose of CTC | 1.000 | No | | | 0.00 | INR Zero Only |
| Total in Figures | | | | | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | | | | | INR Zero Only | |