

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL					
Name of the Work / Contract No:	Dismantling, laying, pipe cutting, jointing etc pipeline Work of 8 inch MS/GI pipeline for pump shifting at coal face as well as 32 No. Sump including repairing of old damaged delivery pipelines as when where required as per advancement of mine under Dakra Project, NK Area			NIT No. GM (NK)/EnM/eNIT/2024-25/122; dated 25.07.2024.	
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SL No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Dismantling of 8" dia pipe	1500.00	Metre		0.00	INR Zero Only
2	Laying and fixing of 8" dia MS pipe.	1870.00	Metre		0.00	INR Zero Only
3	Cutting of MS 8" dia pipe for suitable welding	400.00	Nos		0.00	INR Zero Only
4	Transportation of 8" dia MS pipe from other side to work side.	650.00	Metre		0.00	INR Zero Only
5	Pipe jointing by welding with electrodes	520.00	Nos		0.00	INR Zero Only
6	Fabrication of bends as per requirement	45.00	Nos		0.00	INR Zero Only

7	Dismantling/Fixing of NRV/Sluice Valve	50.00	Nos		0.00	INR Zero Only
8	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	250.25	cum		0.00	INR Zero Only
9	Providing of C.I Heavy Duty NRV size 8"	5.00	Nos		0.00	INR Zero Only
10	Providing of M.S Flange 8"	100.00	Nos		0.00	INR Zero Only
11	Providing of M.S. Nut Bolt and washer 5/8" x 4"	200.00	kg		0.00	INR Zero Only
12	Repairing of old damaged/weaker delivery pipeline approx. 5400 Mtr. With cutting, welding etc work at 10% of 5400 Mtr @ 540 Mtr.	540.00	Metre		0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					