BOQ FOR ITEM RATE QUOTATION BILL OF QUANTITY (BOQ)

NAME OF WORK	"Diversion of power supply cables for lift installation work at Damodar building of Darbhanga House Campus under CCL HQ, Ranchi."			
NIQ NO. & DATE	CCL/HQ/Ranchi/E&M/NIQ/2024-25/ 454 Dt.09.09.2024			
INPUT TAX CREDIT AVAILABLE / NOT AVAILABLE	Available			
Rate of GST (in %)	18%			
STATUS OF BIDDER W.R.T. GST [PLEASE	(a) GST REGISTEREDBIDDER UNDER REGULAR SCHEME			
MARK (√) AS APPLICABLE]	(b) GST REGISTERED BIDDER UNDER COMPOSITION SCHEME			
	(c) GST UNREGISTERED BIDDER			

Sl. No.	Description	Qty	Unit	Rate / Unit in Rs.	Amount in Rs.		
1	Supply of 25 sq. mm, 4 core PVC Insulated and sheathed 1.1 KV copper flexible power cable	70	Mtr				
2	Supply of 25 sq. mm, 3.5 core Aluminum PVC sheathed 1.1 KV armored power cable	70	Mtr				
3	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for 25 sq.mm, 4 core PVC insulated and PVC sheathed /XLPE aluminum conductor cable of 1.1 KV grade as required.	2	No.s				
4	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for 25 sq.mm, 3.5 core PVC insulated and PVC sheathed /XLPE aluminum conductor cable of 1.1 KV grade as required.	2	No.s				
5	Laying of one number PVC insulated and PVC sheeted /XLPE power cable of 1.1 KV grade of 25 sqmm, 4 core direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.	70	Mtr				
6	Laying of one number PVC insulated and PVC sheeted /XLPE power cable of 1.1 KV grade of 25 sqmm, 3.5 core direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.	70	Mtr				
7.	Contractor's profit (on item Sl.no. 1 and 2)	1	LS				
				GST (in Rs.)			
	TOTAL QUOTED AMOUNT in Rs.						

Note: Bidders are requested to quote their rate in figure & words both.

MANAGER(E&M)/M CCL, HQ. RANCHI