

Tender Inviting Authority: Project Engineer(civil),Sawang Colliery, Kathara Area

Making Temporary Hume pipe Culvert Near Railway Under Pass at Sawang GVP PH-II Under Sawang Colliery, Kathara Area

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Item Description/ Heading					
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m all kinds of soil	101.25	m3	188.45	19080.56	INR Nineteen Thousand & Eighty and Paise Fifty Six Only
3	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	6.22	m3	1844.00	11469.68	INR Eleven Thousand Four Hundred & Sixty Nine and Paise Sixty Eight Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 40 mm nominal size derived from natural sources)	11.46	m3	5524.65	63312.49	INR Sixty Three Thousand Three Hundred & Twelve and Paise Forty Nine Only
5	Centering and shuttering including strutting, propping etc. and removal of form work for Foundations, footings, bases for columns	15.72	m2	262.55	4127.29	INR Four Thousand One Hundred & Twenty Seven and Paise Twenty Nine Only
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:134:3 (1 Cement: VA coarse sand (zone-III) derived from natural sources . 3 graded stone aggregate 20 mm nominal size derived from natural sources)	5.40	m3	6944.80	37501.92	INR Thirty Seven Thousand Five Hundred & One and Paise Ninety Two Only
7	Laying Reinforced Cement Concrete Pipe NP4/prestrssed concrete pipe on first class bedding in single row . (Laying Reinforced cement concrete pipe NP4/prestrssed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets 1000 mm dia	18.00	mtr	8910.00	160380.00	INR One Lakh Sixty Thousand Three Hundred & Eighty Only
8	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with Cement mortar 1:6 (1	23.15	m3	5152.20	119273.43	INR One Lakh Nineteen Thousand Two Hundred & Seventy Three and Paise Forty Three Only

9	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand)	3.75	m3	5322.15	19958.06	INR Nineteen Thousand Nine Hundred & Fifty Eight and Paise Six Only
10	12 mm cement plaster finished with a floating coat of neat cement of mix 1:4 (1 cement: 4 fine sand)	37.97	m2	284.75	10811.96	INR Ten Thousand Eight Hundred & Eleven and Paise Ninety Six Only
11	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) Flush/ Ruled pointing	23.25	m2	239.00	5556.75	INR Five Thousand Five Hundred & Fifty Six and Paise Seventy Five Only
12	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and for all lift	20.25	m3	114.40	2316.60	INR Two Thousand Three Hundred & Sixteen and Paise Sixty Only
13	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					453788.74	INR Four Lakh Fifty Three Thousand Seven Hundred & Eighty Eight and Paise Seventy Four Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				