

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority:STAFF OFFICER CIVIL

Name of Work: Washing, painting and cleaning of workshop, plant office rooms, Weighbridge rooms at Kedla Washery under Hazaribagh Area

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Item Description/ Heading					
1.01	White washing with lime to give an even shade: New work (three or more coats)	5759.11	Sqm	14.30	82355.27	INR Eighty Two Thousand Three Hundred & Fifty Five and Paise Twenty Seven Only
1.02	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats) .	804.86	Sqm	38.55	31027.35	INR Thirty One Thousand & Twenty Seven and Paise Thirty Five Only
1.03	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	520.81	Sqm	65.65	34191.18	INR Thirty Four Thousand One Hundred & Ninety One and Paise Eighteen Only
1.04	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed. All kinds of soil	106.25	Cum	128.05	13605.31	INR Thirteen Thousand Six Hundred & Five and Paise Thirty One Only
1.05	Supplying and stacking at site. .Supplying and stacking at site. Moorum.	25.00	Cum	771.15	19278.75	INR Nineteen Thousand Two Hundred & Seventy Eight and Paise Seventy Five Only
1.06	Lettering with black Japan paint of approved brand and manufacture	2500.00	units	3.70	9250.00	INR Nine Thousand Two Hundred & Fifty Only

1.07	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %), total coated thickness with zinc coating 120 gm per sqm as per IS:277 in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	153.36	Sqm	571.00	87568.56	INR Eighty Seven Thousand Five Hundred & Sixty Eight and Paise Fifty Six Only
2.00	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					277276.43	INR Two Lakh Seventy Seven Thousand Two Hundred & Seventy Six and Paise Forty Two Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only