

Percentage BoQ

Tender Inviting Authority: PE (Civil)GM Unit

Name of Work: R/M of drain at Nichu Para,Kargali under GM Unit BnK Area.

	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. All kinds of soil.	40.18	Cum	225.00	9040.50	INR Nine Thousand & Forty and Paise Fifty Only
2	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete	2.670	Cum	898.60	2399.26	INR Two Thousand Three Hundred & Ninety Nine and Paise Twenty Six Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size)	5.350	Cum	5880.35	31459.87	INR Thirty One Thousand Four Hundred & Fifty Nine and Paise Eighty Seven Only
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand	15.560	Cum	5764.25	89691.73	INR Eighty Nine Thousand Six Hundred & Ninety One and Paise Seventy Three Only
5	12 mm cement plaster finished with a floating coat of neat cement: 1:4 (1 cement: 4 fine sand)	93.620	Sqm	301.80	28254.52	INR Twenty Eight Thousand Two Hundred & Fifty Four and Paise Fifty Two Only
6	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					160845.88	INR One Lakh Sixty Thousand Eight Hundred & Forty Five and Paise Eighty Eight Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	