

Item Rate BoQ

| Tender Inviting Authority: Project Engineer(E&M), Gidi-C Colliery,Agada Area, CCL. | | | | | | |
|---|---|----------|-----------------------------|--|-------------------------------------|---|
| Name of the Work / Contract No: | | | | NT No: PE(E&M)/Gidi-C/ENIT/2024-25/13 Dated:13.11.2024 | | |
| Category of Services (To Be Selected by Department) | | | | Category of Bidder (To Be Selected by Bidder) | | |
| ITC Available | Works Contract | | Bidder's Status (Mandatory) | Total GST(in Rs.) | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) |
| Name of the Bidder/ Bidding Firm / Company : | | | Select | 0.00 | 0.00 | 0.00 |
| PRICE SCHEDULE | | | | | | |
| (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) | | | | | | |
| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER # | NUMBER # | TEXT # |
| Sl. No. | Item Description | Quantity | Units | BASIC RATE in Figures To be entered by the Bidder in Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT in Words |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | AMC (for 2 years) including Annual Verification and Stamping of 01 (One) No. 60 MT Capacity Electronic Road Weighbridge of Gidi-C Colliery. Scope: a. Maintenance and Electrical Protection of Digitizer, Junction Boxes, Communication Cables (From Digitizer to Weighment PC and from Digitizer to RFID PC) and Connectors (Digitizer and Computer Communication Cable Connectors, Power Connectors, Load Cell Cable Connectors). Repair and/or Replacement of any or all the above items due to any disturbance viz. Voltage and/or Frequency Disturbance, Earthing Disturbance, Lightening and/or Thundering, Mechanical Damages etc shall be within the Scope of the AMC. Repairing and/or Replacement of Digitizer Motherboard, LED/LCD Display and/or Board, Power Supply Unit and Transformer, Communication Unit, any other Unit/Board/JC within and about the Digitizer damaged due to any disturbance viz. Voltage/Frequency Disturbances, Earthing Disturbances, Lightening/Thundering, Mechanical Damages etc. shall be within the Scope of the AMC. b. Periodic (Bi-monthly) Maintenance and Cleaning of above Equipment. c. Periodic Calibration as and when required by the CCL/LMO(Legal Metrology Officer). d. Annual Verification and Stamping of 60 MT Electronic Road Weighbridge. The job will include Timely Generation and Provision of Online Demand Note for Verification and Stamping Fees, Liaisoning with the Legal Metrology Inspector, Ranggh for issue of Date for Stamping and Verification, supervision and service during Annual Verification and Stamping, and for timely issue of Stamping Certificate. e. Repairing and/or replacement of Load Cells and Load Cell Cables due to any reason except Lightening/Thundering/Mechanical Fatigue Failure. f. Any Statutory fees payable for Annual Verification and Stamping will be borne by CCL. | 2 | Job | | 0.00 | INR Zero Only |
| 2 | Providing & Fixing of Load cells of 30 Te. Capacity or similar electrically and mechanically compatible Load Cell of ISI standard with fitment guarantee on as and when required basis. (Make: Global, Type: WTW) Note: a. During the failure of such Load Cells due to Thundering /Lightening / Mechanical fatigue failure only, the amount quoted by the party for each load cell along with dismantling/removal of old B/d load cell and fixing of new load cell,as applicable for each load cell,will be made on pro-rata basis subject to actual consumption. b. The requirement is projected and tentative concurrent with the AMC Period. The requirement may be higher or on lower side, and, actual payment against the above requirement will be made on pro-rata basis subject to actual consumption. | 8 | Nos. | | 0.00 | INR Zero Only |
| 3 | Cleaning/Loading/Unloading, Testing & Adjustment of 1000 Nos. of 20 Kg each CI Test Weights for Annual Verification and Stamping of 60 MT capacity Weight Track (Global) make Electronic Road Weighbridge installed at Gidi-C Colliery (for 2 years). | 2.00 | Job | | 0.00 | INR Zero Only |
| Total in Figures | | | | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | | | | INR Zero Only | |