

Tender Inviting Authority: Amit Kumar, Dy, Manager(CP), Sawang Washery, Kathara Area

Name of the Work / Contract No:	Providing and fixing of Lightening arrester for complete protection from lightening at inside and outside of Sawang Washery.	NIT No. : SGW/KTA/ENM/E-Tender/2024-25/55	Date- 12.11.2024
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)
Name of the Bidder/ Bidding Firm / Company :	Select	18	0.00
Total GST(in Rs.)		GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
0.00		0.00	0.00

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required (Above 10 mtr. To 12 mtr.)	8.00	nos.			0.00	INR Zero Only
1.02	Supplying & erection of stay set complete galvanized with 19/20mm dia x 1.8 metres long stay rod, anchor plate of size 45cm x 45cm x 7.5mm thick, thimble, stay clamp, turn buckle (20mm x 60mm), 7/4.00 mm dia G.I. stay wire and strain insulator etc. in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone 40mm nominal size) foundation including excavation and refilling etc. as required	8.00	nos.			0.00	INR Zero Only
1.03	Supplying of channel iron 75mm x 40mm x 7.14Kg. Per meter pole cross arm 2 wire O/H line complete with clamp bolts and nuts etc. including drilling holes for insulator pins, bolts and nuts etc. and painting with primer and finish paints as required	16.00	nos.			0.00	INR Zero Only
1.04	Providing and fixing 25mm x 5mm G.I. strip on surface or in recess for connection etc. as required	120.00	mtrs.			0.00	INR Zero Only
1.05	Supply of lightening arrester rod made of copper having length 1 mtr. X 20mm	8.00	nos.			0.00	INR Zero Only
1.06	Supply of nut & bolts	42.00	Pcs.			0.00	INR Zero Only
1.07	Erection of lightening arrester of made od of copper having length 1 mtr. X 20 mmm	8.00	nos.			0.00	INR Zero Only
1.08	Supply and installation of single phase surge protector	6.00	nos.			0.00	INR Zero Only
1.09	Supply of earthing electrode having two custom made G.I. tubes (Galvanized 80 micos, minimum one inside the other of length 3 mtr. (outer dia 80mm) filled with conductor rich crystalline mixture (CCM)	8.00	nos.			0.00	INR Zero Only
1.10	Backfill compound (bag of 25 Kg. each)	16.00	bag			0.00	INR Zero Only

1.11	Earth work in excavation by mechanical means (hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5m, as directed by engineer -in-charge hard rock (blasting prohibited) 1m x 1m x 2.7m x 8 nos. = 21.60 cum	21.60	Cum.			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						