

Validate

Print

Help

**Percentage BoQ**

Tender Inviting Authority: Staff Officer (Civil),CCL, Kathara

**Name of Work:Comprehensive Annual maintenance of Officers colony Including special occasion under Govindpur UG Kathara Area for a period of two years**

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder( To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Not Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE****(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )**

<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER</b>	<b>NUMBER #</b>	<b>TEXT #</b>
<b>Sl. No.</b>	<b>Item Description</b>	<b>Quantity</b>	<b>Units</b>	<b>Estimated Rate in Rs. P</b>	<b>TOTAL AMOUNT in Rs. P</b>	<b>TOTAL AMOUNT in Words</b>
<b>1</b>	<b>2</b>	<b>3</b>	<b>4</b>	<b>5</b>	<b>6</b>	<b>7</b>
1	<b>Item Description/ Heading</b>					
2	Earth work in excv. By mechanical means (Hydraulic excavator)/Manual means in foundation trenches or drains (not exceeding 1.5m in width or 10sqm on plan) incl. Dressing of sides and ramming of bottom lift upto1.5m incl. Getting out the excv. soil and disposal of surplus soil as dir.within a lead of 50m all kind of soil.	112.050	cum	188.45	<b>21115.82</b>	INR Twenty One Thousand One Hundred & Fifteen and Paise Eighty Two Only
3	Providing ,hoisting and fixing upto floor five level precast reinforced cement conc. Work in string courses copings bands bed plates, anchor blocks plain window sills and the like incl. The cost of required centering, shutt. Finishing smooth with 6mm thick cement plaster 1:3 (1cement:3fine sand) on exposed surface compl. Upto but excl. Thecost of reinforcement with 1:2:4(1cement:2 coarsesand:4 graded stone agg. 20mm nominal size.	1.500	cum	8356.10	<b>12534.15</b>	INR Twelve Thousand Five Hundred & Thirty Four and Paise Fifteen Only
4	Reinforcement for RCC work incl. Straightening, cutting, bending, placing in position and binding all complete upto plinth level . Mild steel and medium tensile steel bars.	105.000	kg	75.20	<b>7896.00</b>	INR Seven Thousand Eight Hundred & Ninety Six Only
5	Brick work with FPS bricks of class designation 50 in foundation and plinth in cement mortar 1:6 (1cement :6 coarse sand).	42.720	cum	5322.15	<b>227362.25</b>	INR Two Lakh Twenty Seven Thousand Three Hundred & Sixty Two and Paise Twenty Five Only
6	Brick work with FPS bricks of class designation 50 in superstructure above plinth level upto floor V level in all shapes and sizes in cement mortar 1:6 (1cement:6 coarse sand).	43.313	cum	6494.75	<b>281303.86</b>	INR Two Lakh Eighty One Thousand Three Hundred & Three and Paise Eighty Six Only

7	Half brick masonry with bricks of class design. 50 in foundations and plinth in :cement mortar 1:4 (1cement :4 coarse sand).	27.000	sqm	673.45	<b>18183.15</b>	INR Eighteen Thousand One Hundred & Eighty Three and Paise Fifteen Only
8	Providing wood work in frames of doors, windows, clearstorey windows and other frames, wrought frame and fixed in position sal wood.	2.048	cum	90581.10	<b>185464.80</b>	INR One Lakh Eighty Five Thousand Four Hundred & Sixty Four and Paise Eighty Only
9	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows ISI marked black enamelled MS butt hinges with necessary screws excluding, panelling which will be paid for separately. Klin seasoned and chemically treated Hollock wood. 30 mm thick shutters.	26.400	sqm	1899.75	<b>50153.40</b>	INR Fifty Thousand One Hundred & Fifty Three and Paise Forty Only
10	Providing and fixing panelling or panelling & glazed in panelled and glazed shutters for doors and windows & clerestory windows (area of opening for pannel inserts excl.portion inside grooves rebates to be measured) panelling for panelled or panelled and glazed shutters 25mm to 40mm thick kiln seasoned and chemically treated hollock wood.	0.675	sqm	1720.65	<b>1161.44</b>	INR One Thousand One Hundred & Sixty One and Paise Forty Four Only
11	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	23.400	sqm	1575.70	<b>36871.38</b>	INR Thirty Six Thousand Eight Hundred & Seventy One and Paise Thirty Eight Only
12	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:25 mm thick (for cupboard) including ISI marked nickel plated bright finished M.S. piano hinges with necessary screws	31.350	sqm	1530.60	<b>47984.31</b>	INR Forty Seven Thousand Nine Hundred & Eighty Four and Paise Thirty One Only
13	Providing and fixing factory made PVC door frame of size 50x47mm with a wall thickness of 5mm , made out of extruded 5mm rigid PVC foam sheet mitred at corners and joined with 2 nos. of 150mm long brackets of15x15mm MS square tube, the vetical door profiles to be reinforced with 19x19mm MS square tube of 19 gauge,EPDM rubber gasket weather seal to be provided .. Complete as per manufacturers specification and direction of EIC.	47.500	metre	347.45	<b>16503.88</b>	INR Sixteen Thousand Five Hundred & Three and Paise Eighty Eight Only

14	Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2 ) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing.	13.650	sqm	2092.30	<b>28559.90</b>	INR Twenty Eight Thousand Five Hundred & Fifty Nine and Paise Ninety Only
15	Renewing glass panes, with putty and nails wherever necessary:float glass panes of tickness 4mm.	1.800	sqm	757.10	<b>1362.78</b>	INR One Thousand Three Hundred & Sixty Two and Paise Seventy Eight Only
16	Applying priming coats with primer of approved brand and manufacture, having tow VOC (Volatile Organic Compound) content.: With ready mixed pink or grey primer on wood work (hard and soft wood) having VOC content less than 60 grams/ litre	369.900	sqm	45.45	<b>16811.96</b>	INR Sixteen Thousand Eight Hundred & Eleven and Paise Ninety Six Only
17	Structural steel work in single section fixed with or without connecting plate including cutting hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	318.500	kg	77.95	<b>24827.08</b>	INR Twenty Four Thousand Eight Hundred & Twenty Seven and Paise Eight Only
18	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	900.000	kg	92.55	<b>83295.00</b>	INR Eighty Three Thousand Two Hundred & Ninety Five Only
19	Providing 40x5mm flat iron hold fast 40cm long including fixing to frame with 10mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 mix (1 cement:3 coarse sand :6 graded stone aggregate 20mm nominal size)	120.000	nos	156.45	<b>18774.00</b>	INR Eighteen Thousand Seven Hundred & Seventy Four Only
20	Dismantling doors, windows, and clerestory windows(steel or wood shutters) incl. Choukhats architrave, hold fast etc. compl. And stacking within 50m lead.Of area 3 sqm and below.	40.000	nos	218.95	<b>8758.00</b>	INR Eight Thousand Seven Hundred & Fifty Eight Only
21	Taking out doors, windows and clearstorey windows shutters(steel or wood) including stacking within 50m lead of area 3 sqm and below	80.000	nos	85.20	<b>6816.00</b>	INR Six Thousand Eight Hundred & Sixteen Only

22	Cement conc. Flooring 1:2:4 (1cement:2coarse sand:4 graded stone agg. finished with a floating coat of neat cement including cement slurry, but excluding cost of nosing of steps etc. complete.40mm thick with 20mm nominal size stone agg.	2028.325	sqm	452.50	<b>917817.06</b>	INR Nine Lakh Seventeen Thousand Eight Hundred & Seventeen and Paise Six Only
23	12mm cement plaster mix 1:6 (1cement:6 fine sand.	702.250	sqm	217.70	<b>152879.83</b>	INR One Lakh Fifty Two Thousand Eight Hundred & Seventy Nine and Paise Eighty Two Only
24	Providing and laying in position cement concrete of specified grade excl.the cost of centering and shuttering- All work upto plinth level:1:3:6 (1cement:3coarse sand:6 graded stone agg.20mm nominal size).	3.510	cum	5916.00	<b>20765.16</b>	INR Twenty Thousand Seven Hundred & Sixty Five and Paise Sixteen Only
25	Neat cement punning.	78.000	sqm	55.15	<b>4301.70</b>	INR Four Thousand Three Hundred & One and Paise Seventy Only
26	Demolishing brick work manually/by mechanical means incl.stacking of serviceable materials and disposal of unserviceable materials within 50m lead in cement mortar.	23.625	cum	1194.45	<b>28218.88</b>	INR Twenty Eight Thousand Two Hundred & Eighteen and Paise Eighty Eight Only
27	Dismantling old plaster or skirting ranking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	276.250	sqm	32.00	<b>8840.00</b>	INR Eight Thousand Eight Hundred & Forty Only
28	Providing and fixing on wall face unplasticised Rigid PVC rain water pipe conforming to IS : 13592 type A including jointing with seal ring conforming to IS: 5382 leaving 10mm gap for thermal expansion.single socketed pipes.110mm diameter.	60.000	mtr	262.40	<b>15744.00</b>	INR Fifteen Thousand Seven Hundred & Forty Three and Paise One Hundred Only
29	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion (b)110mm bend.	40.000	nos	114.60	<b>4584.00</b>	INR Four Thousand Five Hundred & Eighty Four Only
30	Providing and fixing unplasticised PVC pipe clips of approved design to unplasticised PVC rain water pipes by means of required length including cutting brick work and fixing in cement mortar 1:4(1cement:4 coarse sand) and making good the wall etc. complete.110mm	30.000	nos	234.80	<b>7044.00</b>	INR Seven Thousand & Forty Four Only
31	Distemping with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound ) content less than 50 gram/ litre, of approved brand and of required said and colour complete to give and even said. Old work (one or more coats).	900.000	sqm	38.55	<b>34695.00</b>	INR Thirty Four Thousand Six Hundred & Ninety Five Only
32	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. One or more coats on old work.	2440.000	sqm	65.65	<b>160186.00</b>	INR One Lakh Sixty Thousand One Hundred & Eighty Six Only
33	Painting with synthetic enamel paint of app.brand and manufacture to give an even shade. Two or more coats on new work.	130.350	sqm	99.90	<b>13021.97</b>	INR Thirteen Thousand & Twenty One and Paise Ninety Seven Only
34	Demolishing cement conc. Manually by mechanical meansincl. Disposal of material within 50m lead as per dir. Of EIC. 1:3:6 or richer mix	50.708	sqm	1412.40	<b>71620.16</b>	INR Seventy One Thousand Six Hundred & Twenty and Paise Sixteen Only

35	CARRIAGE OF MATERIALS By Mechanical Transport including loading,unloading and stacking Lime, moorum, building rubbish Lead - 5 km	156.000	cum	168.10	<b>26223.60</b>	INR Twenty Six Thousand Two Hundred & Twenty Three and Paise Sixty Only
36	Providing and fixing M.S. grills of required pattern in frames of windows with MS flats, square or round bars etc. all compl. Fixed to steel windows by welding.	486.000	kg	145.60	<b>70761.60</b>	INR Seventy Thousand Seven Hundred & Sixty One and Paise Sixty Only
37	Providing reinforced by organic fibres and/or inorganic synthetic fibres cement 6 mm thick corrugated sheets (as per IS: 14871) roofing up to any pitch and fixing with polymer coated J, or L hooks, bolts and nuts 8 mm dia. G.I. plain and bitumen washers or with self drilling fastener and EPDM washers etc. complete (excluding the cost of purlins, rafters and trusses), including cutting sheets to size and shape wherever required.	81.900	sqm	389.10	<b>31867.29</b>	INR Thirty One Thousand Eight Hundred & Sixty Seven and Paise Twenty Nine Only
38	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	15.750	sqm	571.00	<b>8993.25</b>	INR Eight Thousand Nine Hundred & Ninety Three and Paise Twenty Five Only
39	Dismantling roofing including ridges hips valleys and gutter etc. and stacking the materials within 50m lead of G.S. sheet	81.900	sqm	97.70	<b>8001.63</b>	INR Eight Thousand & One and Paise Sixty Three Only
40	Finishing walls with water proofing cement paint of req. shade: Old work (one or more coats @ 2.20 kg/10 sqm) complete.	6527.560	sqm	48.35	<b>315607.53</b>	INR Three Lakh Fifteen Thousand Six Hundred & Seven and Paise Fifty Three Only
41	12mm cement plaster finished with a floating coat of neat cement of mix 1:4 (1 cement:4 fine sand).	592.800	sqm	284.75	<b>168799.80</b>	INR One Lakh Sixty Eight Thousand Seven Hundred & Ninety Nine and Paise Eighty Only
42	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	1040.000	sqm	98.45	<b>102388.00</b>	INR One Lakh Two Thousand Three Hundred & Eighty Eight Only
43	Providing and laying ceramic glazed floor tiles 300x300 mm thickness to be specified by the manufacturer of 1st quality conforming to IS:15622 of approved make in colours, such as white, ivory, grey, fume red brown, laid on 20mm thick cement mortar 1:4 (1 cement:4 coarse sand) including pointing the joints with white cement and matching pigment etc. complete.	22.500	sqm	762.80	<b>17163.00</b>	INR Seventeen Thousand One Hundred & Sixty Three Only

44	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	22.500	sqm	871.30	<b>19604.25</b>	INR Nineteen Thousand Six Hundred & Four and Paise Twenty Five Only
45	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. compl. 300x16mm.	26.000	nos	153.75	<b>3997.50</b>	INR Three Thousand Nine Hundred & Ninety Seven and Paise Fifty Only
46	Providing and fixing ISI marked oxidised MS tower bolt block finish (Barrel type) with necessary screws etc. compl.250x10mm.	26.000	nos	63.60	<b>1653.60</b>	INR One Thousand Six Hundred & Fifty Three and Paise Sixty Only
47	Providing and fixing ISI marked oxidised M.S. handles conformingj to IS:4992 with necessary screws etc. compl. 100mm.	30.000	nos	23.80	<b>714.00</b>	INR Seven Hundred & Fourteen Only
48	Providing and fixing ISI marked oxidised M.S. pressed butt hinges with necessary screws etc. complete. 125x65x2.12 mm	30.000	nos	37.85	<b>1135.50</b>	INR One Thousand One Hundred & Thirty Five and Paise Fifty Only
49	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats	7852.880	nos	89.25	<b>700869.54</b>	INR Seven Lakh Eight Hundred & Sixty Nine and Paise Fifty Four Only
50	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing I paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	196.560	kg	395.15	<b>77670.68</b>	INR Seventy Seven Thousand Six Hundred & Seventy and Paise Sixty Eight Only
51	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	56.160	sqm	824.65	<b>46312.34</b>	INR Forty Six Thousand Three Hundred & Twelve and Paise Thirty Four Only
52	Providing and fixing hard drawn steel wire fabric 75x25 mm mesh of weight not less than 7.75 Kg per sqm to window frames etc. including 62x19 mm beading of second class teak wood and priming coat with approved steel primer all complete.	109.200	sqm	1233.50	<b>134698.20</b>	INR One Lakh Thirty Four Thousand Six Hundred & Ninety Eight and Paise Twenty Only

53	Providing and fixing Stainless Steel AISI 304 (18/8) kitchen sink as per IS 13983 with C.I. brackets and stainless steel plug 40 mm including painting of fittings and brackets, cutting and making good the walls wherever required: 470X420 mm bowl depth 178 mm	6.000	nos	2437.30	<b>14623.80</b>	INR Fourteen Thousand Six Hundred & Twenty Three and Paise Eighty Only
54	Providing and fixing white vitreous china water closet squatting pan (Indian type).(b) Orissa pattern W.C pan of size 580x440mm.	6.000	nos	2294.00	<b>13764.00</b>	INR Thirteen Thousand Seven Hundred & Sixty Four Only
55	Providing and fixing white vitreous china pedestal type (European type/wash down type) water closet pan.	6.000	nos	1986.20	<b>11917.20</b>	INR Eleven Thousand Nine Hundred & Seventeen and Paise Twenty Only
56	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : 100 mm inlet and 100 mm outlet Sand Cast Iron S&S as per IS- 1729	6.000	nos	1117.90	<b>6707.40</b>	INR Six Thousand Seven Hundred & Seven and Paise Forty Only
57	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:White Vitreous China Flat back wash basin size 550x 400 mm with single 15 mm C.P. brass pillar tap	8.000	nos	1458.10	<b>11664.80</b>	INR Eleven Thousand Six Hundred & Sixty Four and Paise Eighty Only
58	Providing and fixing PVC low level flushing cistern with manually controlled device (handle lever) conforming to IS 7231 .with all fittings and fixtures complete (a) 10 litre capacity - white	25.000	nos	863.00	<b>21575.00</b>	INR Twenty One Thousand Five Hundred & Seventy Five Only
59	Providing and fixing GI pipes complete with GI fittings and clamps, including cutting and making good the walls etc.(a).15mm dia nominal bore.	35.000	m	244.70	<b>8564.50</b>	INR Eight Thousand Five Hundred & Sixty Four and Paise Fifty Only
60	Providing and fixing GI pipes complete with GI fittings and clamps, including cutting and making good the walls etc.(a).20mm dia nominal bore.	45.000	m	302.85	<b>13628.25</b>	INR Thirteen Thousand Six Hundred & Twenty Eight and Paise Twenty Five Only
61	Providing and fixing GI pipes complete with GI fittings and clamps, including cutting and making good the walls etc.(a).25mm dia nominal bore.	45.000	m	403.20	<b>18144.00</b>	INR Eighteen Thousand One Hundred & Forty Four Only
62	Providing and fixing GI pipe compl. With GI fittings incl. Trenching and refilling etc.(external work.) 40mm dia nominal bore.	60.000	m	460.20	<b>27612.00</b>	INR Twenty Seven Thousand Six Hundred & Twelve Only
63	Providing and fixing GI pipe compl. With GI fittings incl. Trenching and refilling etc.(external work.) 50mm dia nominal bore.	45.000	m	543.40	<b>24453.00</b>	INR Twenty Four Thousand Four Hundred & Fifty Three Only
64	Providing and fixing GI pipe compl. With GI fittings incl. Trenching and refilling etc.(external work.) 80mm dia nominal bore.	45.000	m	768.15	<b>34566.75</b>	INR Thirty Four Thousand Five Hundred & Sixty Six and Paise Seventy Five Only
65	Dismantling GI pipes (external work) including excv. And refilling trenches after taking out the pipes,manually/by mechanical means incl. stacking of pipes within 50m. Leas as per direction of EIC:a) 15mm to 40mm nominal bore.	90.000	m	88.85	<b>7996.50</b>	INR Seven Thousand Nine Hundred & Ninety Six and Paise Fifty Only

66	Dismantling GI pipes (external work) including excv. And refilling trenches after taking out the pipes,manually/by mechanical means incl. stacking of pipes within 50m. Leas as per direction of EIC:b) above 40mm nominal bore.	90.000	m	97.70	<b>8793.00</b>	INR Eight Thousand Seven Hundred & Ninety Three Only
67	Labour cost for fixing GI pipes complete with GI fittings and clamps, including cutting and making good the walls etc.(a).15mm dia nominal bore.	75.000	m	131.55	<b>9866.25</b>	INR Nine Thousand Eight Hundred & Sixty Six and Paise Twenty Five Only
68	Labour cost for fixing GI pipes complete with GI fittings and clamps, including cutting and making good the walls etc.(a).20mm dia nominal bore.	90.000	m	145.20	<b>13068.00</b>	INR Thirteen Thousand & Sixty Seven and Paise One Hundred Only
69	Labour cost for fixing GI pipes complete with GI fittings and clamps, including cutting and making good the walls etc.(a).25mm dia nominal bore.	90.000	m	159.45	<b>14350.50</b>	INR Fourteen Thousand Three Hundred & Fifty and Paise Fifty Only
70	Labour cost for GI pipe compl. With GI fittings incl. Trenching and refilling etc.(external work.) 40mm dia nominal bore.	90.000	m	118.00	<b>10620.00</b>	INR Ten Thousand Six Hundred & Twenty Only
71	Labour cost for GI pipe compl. With GI fittings incl. Trenching and refilling etc.(external work.) 50mm dia nominal bore.	90.000	m	118.00	<b>10620.00</b>	INR Ten Thousand Six Hundred & Twenty Only
72	Providing and fixing CI sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately): 100mm dia. Class I 100mm dia. Class II	10.000	m	3830.40	<b>38304.00</b>	INR Thirty Eight Thousand Three Hundred & Four Only
73	Providing and fixing gun metal gate valve with CI wheel of approved quality (screwed end): 40mm nominal bore.	15.000	m	614.05	<b>9210.75</b>	INR Nine Thousand Two Hundred & Ten and Paise Seventy Five Only
74	Providing and fixing gun metal gate valve with CI wheel of approved quality (screwed end): 50mm nominal bore.	15.000	m	762.45	<b>11436.75</b>	INR Eleven Thousand Four Hundred & Thirty Six and Paise Seventy Five Only
75	Providing and placing on terrace (at all floor levels) polye-thylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holesfor inlet,outlet and overflow pipes but without fittings and the base support for tank.	15000.000	litrs	8.40	<b>126000.00</b>	INR One Lakh Twenty Six Thousand Only
76	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipe, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings I/c fixing the pipe with clamps at 1.00 m specing. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching,refiling & testing of joints complete as per direction Of EIC External work 20mm nominal outer dia pipes.	120.000	metre	217.35	<b>26082.00</b>	INR Twenty Six Thousand & Eighty Two Only
77	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipe, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings I/c fixing the pipe with clamps at 1.00 m specing. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching,refiling & testing of joints complete as per direction Of EIC External work 25mm nominal outer dia pipes.	105.000	metre	298.65	<b>31358.25</b>	INR Thirty One Thousand Three Hundred & Fifty Eight and Paise Twenty Five Only
78	cleaning of mannuar from septic tank and inspection chamber	77.357	cum	1137.75	<b>88012.78</b>	INR Eighty Eight Thousand & Twelve and Paise Seventy Eight Only



79	Providing ,hoisting and fixing upto floor five level precast reinforced cement conc. Work in string courses copings bands bed plates, anchor blocks plain window sills and the like incl. The cost of required centering, shutt. Finishing smooth with 6mm thick cement plaster 1:3 (1cement:3fine sand) on exposed surface compl. Upto but excl. Thecost of reinforcement with 1:2:4(1cement:2 coarsesand:4 graded stone agg. 20mm nominal size.	23.389	cum	8356.10	<b>195438.73</b>	INR One Lakh Ninety Five Thousand Four Hundred & Thirty Eight and Paise Seventy Three Only
80	12mm cement plasteer finished with a floating coat of neat cement of mix 1:4 (1cement:4 fine sand).	309.025	sqm	284.75	<b>87994.87</b>	INR Eighty Seven Thousand Nine Hundred & Ninety Four and Paise Eighty Seven Only
81	Reinforcement for RCC work incl. Straightening, cutting, bending, placing in position and binding all complete upto plinth level .Thermo-Mechanically Treated bars	1637.213	kg	75.85	<b>124182.57</b>	INR One Lakh Twenty Four Thousand One Hundred & Eighty Two and Paise Fifty Seven Only
82	Providing and fixing brass bib cock of approved quality. (a) 15mm dia nominal bore.	30.000	nos	263.75	<b>7912.50</b>	INR Seven Thousand Nine Hundred & Twelve and Paise Fifty Only
83	Providing and fixing brass stop cock of approved quality:a)15mm nominal bore	30.000	nos	263.75	<b>7912.50</b>	INR Seven Thousand Nine Hundred & Twelve and Paise Fifty Only
84	Providing and fixing uplasticised PVC connection pipe with brass unions : 15 mm nominal bore	30.000	nos	73.95	<b>2218.50</b>	INR Two Thousand Two Hundred & Eighteen and Paise Fifty Only
85	Providing and fixing GI Union in existing GI pipe line, cutting & threading the pipe and making long screws incl. excavation refilling the earth or cutting of wall & making good the same compl. Wherever required. 15mm nominal bore.	20.000	nos	526.55	<b>10531.00</b>	INR Ten Thousand Five Hundred & Thirty One Only
86	Providing and fixing GI Union in existing GI pipe line, cutting & threading the pipe and making long screws incl. excavation refilling the earth or cutting of wall & making good the same compl. Wherever required. 20mm nominal bore.	15.000	nos	549.80	<b>8247.00</b>	INR Eight Thousand Two Hundred & Forty Seven Only
87	Providing and fixing GI Union in existing GI pipe line, cutting & threading the pipe and making long screws incl. excavation refilling the earth or cutting of wall & making good the same compl. Wherever required. 25mm nominal bore.	15.000	nos	619.45	<b>9291.75</b>	INR Nine Thousand Two Hundred & Ninety One and Paise Seventy Five Only
88	Providing and fixing GI Union in existing GI pipe line, cutting & threading the pipe and making long screws incl. excavation refilling the earth or cutting of wall & making good the same compl. Wherever required. 40mm nominal bore.	20.000	nos	753.05	<b>15061.00</b>	INR Fifteen Thousand & Sixty One Only
89	Providing and fixing GI Union in existing GI pipe line, cutting & threading the pipe and making long screws incl. excavation refilling the earth or cutting of wall & making good the same compl. Wherever required. 50mm nominal bore.	20.000	nos	1021.05	<b>20421.00</b>	INR Twenty Thousand Four Hundred & Twenty One Only
90	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : (a) 15mm dia nominal bore.	15.000	nos	376.95	<b>5654.25</b>	INR Five Thousand Six Hundred & Fifty Four and Paise Twenty Five Only
91	Providing and fixing PTMT bib cock of approved quality and colour.15mm nominal bore, 86mm long. Weighing not less than 88 gms.	30.000	nos	95.35	<b>2860.50</b>	INR Two Thousand Eight Hundred & Sixty and Paise Fifty Only

92	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately): 50mm diameter	20.000	nos	3569.05	<b>71381.00</b>	INR Seventy One Thousand Three Hundred & Eighty One Only
93	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately):80 mm diameter	20.000	nos	4730.55	<b>94611.00</b>	INR Ninety Four Thousand Six Hundred & Eleven Only
94	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately): 40mm diameter	20.000	nos	2872.15	<b>57443.00</b>	INR Fifty Seven Thousand Four Hundred & Forty Three Only
95	Brooming and cleaning of all roads in colony and other places as required with all tools & tackles and stacking the garbage at specified places as per instruction of Engineer-in-charge.	630000.000	sqm	0.25	<b>157500.00</b>	INR One Lakh Fifty Seven Thousand Five Hundred Only
96	Collection of garbage from door to door and disposal the same through trolley or other available arrangement to the specified place within a lead of 1 KM including sweeping of stair case with all tools and tackles complete as per instruction of Engineer-in-charge. Ground floor	27010.000	nos	6.24	<b>168542.40</b>	INR One Lakh Sixty Eight Thousand Five Hundred & Forty Two and Paise Forty Only
97	Cleaning of surface drain including disposal of mud, sludge through trolley or other arrangements to a specified place (in no case it shall be kept on drain banks) within a lead of 1KM complete with all tools & tackles as per instruction of EIC : Upto 300 mm wide	2175.600	mtr	2.50	<b>5439.00</b>	INR Five Thousand Four Hundred & Thirty Nine Only
98	Cleaning of surface drain including disposal of mud, sludge through trolley or other arrangements to a specified place (in no case it shall be kept on drain banks) within a lead of 1KM complete with all tools & tackles as per instruction of EIC : Above 300 mm and upto 600mm	4200.000	mtr	3.12	<b>13104.00</b>	INR Thirteen Thousand One Hundred & Four Only
99	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	11520.000	sqm	10.20	<b>117504.00</b>	INR One Lakh Seventeen Thousand Five Hundred & Three and Paise One Hundred Only
100	CARRIAGE OF MATERIALS 1.1 By Mechanical Transport including loading ,unloading and stacking Earth 5 km	166.500	cum	210.10	<b>34981.65</b>	INR Thirty Four Thousand Nine Hundred & Eighty One and Paise Sixty Five Only
101	Cleaning of terrace/loft water storage tank (inside surface area) upto 2000 litre capacity at all heights with coconut brushes, duster etc., removal of silt, rubbish from the tank and cleaning the tank with fresh water disinfecting with bleaching powder @ 0.5gm per litre capacity of tank including marking the date of cleaning on the side of tank body with the help of stencil and paint and disposing of malba all complete as per direction of Engineer-in-Charge. (The old date already written on tank should be removed with paint remover or black paint and if date is not written with the stencil or old date is not removed deduction will be made @ Rs. 0.10 per litre) (if during cleaning any GI fittings or ball cock is damaged that is to be repaired by contractor at his own cost and nothing extra will be paid on this account).	37000.000	litrs	0.30	<b>11100.00</b>	INR Eleven Thousand One Hundred Only
102	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	<b>0.00</b>	<b>0.00</b>	INR Zero Only

Total in Figures			<b>6114189.91</b>	INR Sixty One Lakh Fourteen Thousand One Hundred & Eighty Nine and Paise Ninety One Only
Quoted Rate in Figures		Select	<b>0.00</b>	INR Zero Only
Quoted Rate in Words	<b>INR Zero Only</b>			











































































































































































